

ROW COOLER EQUIPERNT SCHDULE														
UNIT NO.	LOCATION	Room Name	QTY	AIR VOLUME (CMH)	冷卻盤管 COOLING COIL DATA					輸入功率 INPUT POWER		加熱量 CAPACITY	再熱器 容量 CAPACITY	REMARK
					能量 COOLING CAPACITY (Kw)	水 流 量 WATER FLOW (LPM)	進水溫度 ENTERING WATER TEMP (°C)	出水溫度 WATER TEMP (°C)	入口溫度 ENTERING AIR TEMP (°CDB)	KW	PH/VOLT/Hz			
DC3-RC-01	FAB L20(IN)	DC3	1	14050	96	150	5	14	40.6	4.8	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-02	FAB L20(IN)	DC3	1	14050	96	150	5	14	40.6	4.8	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-03	FAB L20(IN)	DC3	1	14050	96	150	5	14	40.6	4.8	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-04	FAB L20(IN)	DC3	1	14050	96	150	5	14	40.6	4.8	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-05	FAB L20(IN)	DC3	1	14050	96	150	5	14	40.6	15.8	3Φ-380/220V-60HZ	3kg/hr	8.1 KW	(恆溫恆濕)
DC3-RC-06	FAB L20(IN)	DC3	1	14050	96	150	5	14	40.6	4.8	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-07	FAB L20(IN)	DC3	1	11400	70	132	5	14	40.6	3	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-08	FAB L20(IN)	DC3	1	11400	70	132	5	14	40.6	3	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-09	FAB L20(IN)	DC3	1	11400	70	132	5	14	40.6	3	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-10	FAB L20(IN)	DC3	1	11400	70	132	5	14	40.6	3	3Φ-380/220V-60HZ	-	-	(單冷)
DC3-RC-11	FAB L20(IN)	DC3	1	11400	70	132	5	14	40.6	14	3Φ-380/220V-60HZ	3kg/hr	8.1 KW	(恆溫恆濕)
DC3-RC-12	FAB L20(IN)	DC3	1	11400	70	132	5	14	40.6	3	3Φ-380/220V-60HZ	-	-	(單冷)

OWNER / DEVELOPER			
 ARCHITECTURAL CONSULTANT			
JJP ARCHITECTS & PLANNERS 潘冀聯合建築師			
CIVIL & STRUCTURAL CONSULTANT			
TEAM 群策工程股份有限公司			
MECHANICAL & ELECTRICAL CONSULTANT & CONTRACTOR			
uis United Integrated Services 漢唐集成股份有限公司			
SUB-CONTRACTOR			
PROJECT ADDRESS			
KEY PLAN			
PROJECT TITLE			
Micron Falcon A Project (200K)			
PROJECT PHASE			
Concept Design			
DRAWING TITLE			
EQUIPMENT SCHEDULE			
-			
-			
-			
DESIGNED : JACK CHANG			
DRAWN : JACK CHANG			
CHECKED : C.S.HU			
DATE : 2024/11/20		JOB NO. :	
SCALE : N.T.S		REV	
DRAWING NO.		0	
DE_F1_DATA_B001_M_HVAC_6001-DC-00		SIZE	
SHEET:		A1	