OIL-FREE SCREW TYPE COMPRESSOR SCHEDULE

UNIT MARK	SERVICE	TYPE	CAPACITY NCMH	DISCHARGE PRESSURE kg/cm2	1st & 2nd STAGE COOLING WATER				MOTOR			WEIGHT KGS	REMARKS
					FLOW RATE(LPM)	EWT.(°C)	LWT(°C)	DROP PRESS.(mAq)	KW	VOLTAGE	TYPE		
FAL-CDA-SAC-101	CLEANROOM & UTILITIES CLEAN DRY AIR	SCREW	4500	9.5	585	12	20	5	280	3/--/60	TEFC	12500	1. MOTOR WITH VFD & "VSD"/ THERMAL SWITCHS. 2 WITH AUTODRAIN.(FUTURE).
FAL-CDA-SAC-102	CLEANROOM & UTILITIES CLEAN DRY AIR	SCREW	4500	9.5	585	12	20	5	280	3/--/60	TEFC	12500	1. MOTOR WITH VFD & "VSD"/ THERMAL SWITCHS. 2 WITH AUTODRAIN.(FUTURE).

OIL-FREE CENTRIFUGAL TYPE COMPRESSOR SCHEDULE

UNIT MARK	SERVICE	TYPE	CAPACITY NCMH	DISCHARGE PRESSURE kg/cm2	1st & 2nd STAGE COOLING WATER &AFTER COOLING WATER								MOTOR			WEIGHT KGS	REMARKS
					FLOW RATE(LPM)	EWT.(°C)	LWT(°C)	DROP PRESS.(mAq)	FLOW RATE(CMH)	EWT.(°C)	LWT(°C)	DROP PRESS.(mAq)	HP	VOLTAGE	TYPE		
FAL-CDA-CMP-1~4	CLEANROOM & UTILITIES CLEAN DRY AIR	CENTRIFUGAL	4400	8.6 Bar	--	29	35	--	--	29	35	--	600	3/6600/60	--	--	既有的設備(50K)
FAL-CDA-AC-101	CLEANROOM & UTILITIES CLEAN DRY AIR	CENTRIFUGAL	6000	9.5	825	29	35	5	--	--	--	--	850	3/6600/60	TEFC	8680	1. MOTOR WITH THERMAL SWITCHS. 2 WITH AUTODRAIN . (FUTURE).
FAL-CDA-AC-102	CLEANROOM & UTILITIES CLEAN DRY AIR	CENTRIFUGAL	6000	9.5	825	29	35	5	--	--	--	--	850	3/6600/60	TEFC	8680	1. MOTOR WITH THERMAL SWITCHS. 2 WITH AUTODRAIN . (200K).
FAL-CDA-AC-103	CLEANROOM & UTILITIES CLEAN DRY AIR	CENTRIFUGAL	6000	9.5	825	29	35	5	--	--	--	--	850	3/6600/60	TEFC	8680	1. MOTOR WITH THERMAL SWITCHS. 2 WITH AUTODRAIN . (FUTURE).
FAL-CDA-AC-104	CLEANROOM & UTILITIES CLEAN DRY AIR	CENTRIFUGAL	6000	9.5	825	29	35	5	--	--	--	--	850	3/6600/60	TEFC	8680	1. MOTOR WITH THERMAL SWITCHS. 2 WITH AUTODRAIN . (FUTURE).

HEAT REGENERATED ADSORPTION AIR DRYER SCHEDULE

UNIT MARK	SERVICE	CAPACITY(INLET) NCMH	INLET TEMP. & RH (°C/%)	INLET PRESSURE kg/cm2G (2)	PRESSURE DROP kg/cm2	OUTLET DEWPOINT °C (3)	POWER SUPPLY			COOLING WATER			PREFILTER			AFTER FILTER			WEIGHT KGS	REMARKS
							HEATRE GROUP (KW)	BLOWER (KW)	ELECTRICAL	FLOW RATE LPM	EWT.(°C)	LWT(°C)	TYPE	PARTICLE(um)	OIL(mg/m^3) LIQUID	TYPE	PARTICLE(um)	OIL(mg/m^3) LIQUID		
FAL-CDA-DR-101	CLEANROOM & UTILITIES CLEAN DRY AIR	>6500	40/100	9.5/8	0.45	-80/-90	110	20	3/380/60	100	12	19	SCREWED CONNECTION (WITH AUTODRAIN)	<= 0.5	<= 0.03	SCREWED CONNECTION (WITH MANUAL DRAIN)	<= 0.1	<= 0.003	2200	(FUTURE).
FAL-CDA-DR-102	CLEANROOM & UTILITIES CLEAN DRY AIR	>6500	40/100	9.5/8	0.45	-80/-90	110	20	3/380/60	100	12	19	(WITH AUTODRAIN)	<= 0.5	<= 0.03	(WITH MANUAL DRAIN)	<= 0.1	<= 0.003	2200	(200K).
FAL-CDA-DR-103	CLEANROOM & UTILITIES CLEAN DRY AIR	>6500	40/100	9.5/8	0.45	-80/-90	110	20	3/380/60	100	12	19	(WITH AUTODRAIN)	<= 0.5	<= 0.03	(WITH MANUAL DRAIN)	<= 0.1	<= 0.003	2200	(50K).
FAL-CDA-DR-104	CLEANROOM & UTILITIES CLEAN DRY AIR	>6500	40/100	9.5/8	0.45	-80/-90	110	20	3/380/60	100	12	19	(WITH AUTODRAIN)	<= 0.5	<= 0.03	(WITH MANUAL DRAIN)	<= 0.1	<= 0.003	2200	(50K).
FAL-CDA-DR-105	CLEANROOM & UTILITIES CLEAN DRY AIR	>6500	40/100	9.5/8	0.45	-80/-90	110	20	3/380/60	100	12	19	(WITH AUTODRAIN)	<= 0.5	<= 0.03	(WITH MANUAL DRAIN)	<= 0.1	<= 0.003	2200	(50K).
FAL-CDA-DR-106	CLEANROOM & UTILITIES CLEAN DRY AIR	>6500	40/100	9.5/8	0.45	-80/-90	110	20	3/380/60	100	12	19	(WITH AUTODRAIN)	<= 0.5	<= 0.03	(WITH MANUAL DRAIN)	<= 0.1	<= 0.003	2200	(50K).

NOTE. (1) PREFILTER WITH AUTODRAIN ; (2) OPERATING PRESSURE / DETECTION OF PRESSURE ; (3) OPERATING DEWPOINT / DETECTION OF DEWPOINT. (4) INCLUDING FINAL FILTER PARTICLE:<=0.003um,OIL:<=0.003mg/m^3 ,MATERIAL : PTFE.

NOTE. (1) PREFILTER WITH AUTODRAIN ; (2) OPERATING PRESSURE / DETECTION OF PRESSURE ; (3) OPERATING DEWPOINT / DETECTION OF DEWPOINT. (4) INCLUDING FINAL FILTER PARTICLE:<=0.003um,OIL:<=0.003mg/m^3 ,MATERIAL : PTFE.

AIR RECEIVER TANK SCHEDULE

UNIT MARK	SERVICE	CAPACITY M3	PRESSURE Bar-G	MATERIAL	REMARKS
FAL-CDA-RT-101	CLEANROOM & UTILITIES CLEAN DRY AIR	>22	<12.0 (MAX)	SUS304	1. W/SAFETY VALVE, PRESSURE VALVE, AUTO DRAIN TRAP. . (50K).
FAL-CDA-RT-102	CLEANROOM & UTILITIES CLEAN DRY AIR	>22	< 12.0 (MAX)	SUS304	1. W/SAFETY VALVE, PRESSURE VALVE, AUTO DRAIN TRAP. . (50K).

OWNER / DEVELOPER

micron

ARCHITECTURAL CONSULTANT

JJP ARCHITECTS & PLANNERS 潘冀聯合建築師

CIVIL & STRUCTURAL CONSULTANT

TEAM 群策工程股份有限公司

MECHANICAL & ELECTRICAL CONSULTANT & CONTRACTOR

UIS United Integrated Services 漢唐集成股份有限公司

SUB-CONTRACTOR

PROJECT ADDRESS

KEY PLAN

REV	DATE	DESCRIPTION	ISSUED BY
A	2025/01/02	REVIEW Drawing	

Revisions

PROJECT TITLE

Micron Falcon A Project (200K)

PROJECT PHASE

Concept Design

DRAWING TITLE

EQUIPMENT SCHEDULE
CDA SYSTEM - 1
-

DESIGNED : CHEN	DRAWN : CHEN	CHECKED : CHUNGSIR	
DATE : 2024/11/20	JOB NO. :	SCALE : N.T.S.	
DRAWING NO. DE_F1_ALL_B0001_D_ACDA_0001-00			REV 0
		SHEET:	SIZE A1