

SECTION 01001A-A

CONSTRUCTION PROGRESS DOCUMENTATION

1.0 CONTRACT SCHEDULE AND DOCUMENT CONTROL

A. Project Schedule:

1. At a minimum, the project schedule shall contain the following items:
 - a. Time for mobilization.
 - b. Issuance of required permits.
 - c. Preparation and submittal of shop drawings and samples.
 - d. Review of shop drawings and other submittals. Duration shall not be less than the review time specified unless clearly identified and prior written acceptance has been obtained from the Engineer.
 - e. Order, manufacture, delivery, and installation dates of major equipment and critical materials. Identify items that impact the critical path because of delivery period.
 - f. Listing of major schedule activities of other contractors with deadline or time frame for completion arranged to show phases of work in the same categories as required in the application for payment. Unless otherwise approved by Owner, duration shall not be less than 1 day nor more than 10 working days.
 - g. Identification of predecessors and successors for each scheduled activity.
 - h. Testing and checkout of equipment and systems.
 - i. Ready date for inspection.
 - j. Contract substantial completion date.
 - k. Contract final completion date.
2. At a minimum, the project schedule shall show for each phase of work and for work as a whole:
 - a. Date of commencement.
 - b. Date of completion.
 - c. Anticipated percent of completion at each monthly cutoff date.
 - d. Resource-loaded schedule activities by one of the following: percent the value of each work feature is to the value of the entire work; cost of each activity from the approved schedule of values; and labor hours associated with each schedule activity.

3. Participate with other contractors and the Owner in the review of their individual schedules. Make revisions to the project schedule after joint review and mutual agreement. A consolidation of the agreed individual schedules shall constitute the overall project schedule to be used until subsequently revised.
4. Include with the approved project schedule a resource report indicating the number of craft required on a weekly basis to complete each phase of the work. Submit daily a workforce report showing the number of craft employed each day on this project by trade. Also indicate in this report, major construction equipment on-site and materials received on site with the actual delivery dates. Include any schedule coordination requirements or situations impacting the project schedule on this daily workforce report.
5. Furnish a detailed and complete material list 1-week after approval of the schedule. Maintain the materials list to indicate status of its procurement consistent with the approved project schedule as requested by the Owner. Furnish copies of unpriced purchase orders indicating date of order and firm delivery dates for such materials. Advise Owner immediately of potential delivery problems so that other action may be considered.
6. The Owner will schedule and coordinate the activities of the contractors in accordance with the overall project schedule using information supplied by all contractors.
7. Submit progress reports on a monthly basis to show at a minimum:
 - a. Material status for major procurement items and/or fabricated and manufactured equipment indicating:
 - 1) Shop drawing and product data submittal and Engineer review and acceptance dates.
 - 2) Date purchase order submitted.
 - 3) Shipment and delivery dates.
 - 4) Expediting report.
 - 5) Summary of major items on site and items installed.
 - b. Submittal log showing:
 - 1) Transmittal date.
 - 2) Engineer review status and date.
 - 3) Action required.
 - c. Status of permits and regulatory required actions.
 - d. Progress history including percent complete of tasks shown on progress schedule.

- e. Summary of subcontractor activity.
 - f. Onsite and offsite work force levels by craft and other functions.
 - g. Workforce loading plan showing graphically the number of workers required on site over time.
 - h. A cumulative percent complete plan showing a graphical comparison of the planned percent completion and the actual percent completion of work.
- 8. 1 day before the weekly progress meeting, submit an updated schedule to the Owner and bring an updated 3-week look ahead and 1-week back schedule to the weekly coordination meeting. Consider and coordinate with the work of other contractors in this planning.
 - 9. Submit a report by 10:00 a.m. on a daily basis that shall include a brief description of the previous day's activities, work force and schedule and note any significant problems. This information shall be part of the daily workforce report required above.
 - 10. Provide test and inspection reports within 2 working days following the test. Provide such other reports as may be required by Owner for the purpose of monitoring, conducting and expediting work.
 - 11. If at any time during the project Contractor fails to complete an activity by its latest scheduled completion date, submit a written statement, within 5 work days, as to how and when it will reorganize its work force to return to schedule.
 - 12. Furnish other progress reports as may reasonably be required to ensure optimum evaluation of progress.

B. Document Control:

- 1. Project Forms: In addition to the forms included or specified elsewhere, the following forms will be used by the Owner and Contractor in the administration of the Contract.
 - a. Change Order.
 - b. Change Order Log.
 - c. Construction Change Directive.
 - d. Field Order.
 - e. Field Order Log.
 - f. Submittal Log.
 - g. Design Clarification Notice (DCN).
 - h. Design Clarification Notice Log.
 - i. Application for Payment.
 - j. Application for Payment Detail Sheet.
 - k. Affidavit for Final Waiver of Lien.
 - l. Certificate Of Substantial Completion.
 - m. Notice of Discrepancy (NOD).

- n. Notification of Discrepancy Log.
- o. Remedial Action Request (RAR).
- p. Request For Information (RFI).
- q. Request For Information Log.
- r. Request for Quotation (RFQ) (For Changes).
- s. Notice of Transfer to Contractor Log.
- t. Notice of Transfer to Owner Log.
- u. Materials and Equipment Inspection Log.
- v. Punch List.
- w. Site Observation Reports (SOR)
- x. Work List

2. Project Documents:

- a. Clearly label each document Contract Documents in neat, large, bold, red printed letters. The first sheet shall also be clearly labeled in red with the

names, addresses, and phone numbers of the Contractor and each of its subcontractors as applicable and shall be signed by the Contractor.

- b. Store Contract Documents and samples in field office apart from copies of such documents used for construction. Provide files, racks, and secure storage for such Contract Documents and samples. Maintain Contract Documents in a clean, dry, and legible condition. Do not remove from field office. Use copies of the Contract Documents for construction purposes in the field.

- c. Drawings and Shop Drawings:

- 1) Maintain one full-size set of reproducible project drawings as a Contract Document (Record Drawings) at the time work is commenced.

- a) Update these Record Drawings as work progresses to reflect the as-constructed condition of facilities included in the Contract, including work added to the Contract which is not shown on the Drawings or where shown schematically. Using erasable colored pencils (not ink or indelible pencil), clearly indicate additions, deletions, and changes according to the following color code:
 - (1) Green: information or work deleted from the Drawings or not installed as shown.
 - (2) Red: information or work added to the Drawings or modifications.
 - (3) Blue: notes or clarifications.

- b) Mark to indicate actual installation where installation varies appreciably from installation shown originally. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later. Do not conceal work until required information is recorded.
 - c) Accurately mark the Drawings or shop drawings, whichever are most capable of showing actual physical conditions. Where shop drawings are marked, show cross reference to the Record Drawing location.
 - d) Note construction change directive numbers, alternate numbers, change order numbers, and similar identification.
- 2) Legibly mark each item to record actual construction using the same legends as used in the Contract Documents, including:
- a) Measured depths of elements of foundation in relation to finish floor datum.
 - b) Measured horizontal and vertical locations of underground utilities and appurtenances referenced to visible and accessible features of construction.
 - c) Measured locations of internal utilities and appurtenances concealed in construction referenced to visible and accessible features of construction.
 - d) Drawings indicate the exact routing of piping, ductwork, power control, communication wiring, etc., location and function of controls, and whether manual or automatic and normal amperage readings for motors taken at the equipment under normal load conditions.
 - e) Field changes of dimension and detail.
 - f) Changes made by change order.
- 3) Before submitting each application for payment, review Record Drawings with the Owner and obtain the Owner's written concurrence for submission with application for payment. The purpose of these meetings is to review changes to Record Drawings made since last review and review documentation of as-installed conditions. Failure to review Record Drawings and obtain written

concurrence may result in withholding Contractor's payment.

d. Specifications: Accurately mark to indicate.

- 1) Actual installation where installation varies substantially from that indicated in the Contract Documents and changes issued. Note related project drawing information where applicable. Give particular attention to substitutions, selection of product options, and information on concealed installations that would be difficult to identify or measure and record later.
- 2) Manufacturer, trade name, and catalog number of each product actually installed particularly optional items and substitute items.
- 3) Changes made by addenda, change order, or field order.

e. At completion of work, certify, by endorsement thereof, that each as-built document is complete and accurate.

f. Deliver certified as-built documents to the Owner as a condition of acceptance, prior to final application for payment and within 45 days of final acceptance of work by the Owner unless otherwise modified by the Contract.

3. A request for information (RFI) shall be completed and submitted to the Owner whenever the Contractor deems the need for clarification relative to Specifications, Drawings, or any part of construction are needed. The Owner will forward the request to the appropriate party for evaluation and decisions. The Contractor will receive a preliminary response within 5 working days with a final response to follow. A RFI may or may not generate a Change Order.

4. Warranties and Bonds:

a. Form of Submittals: Submit warranties, certificates, and bonds required by the Contract as described below.

- 1) Bind in commercial-quality A4 three-ring binders with hardback, cleanable, plastic covers.
- 2) Label cover of each binder with typed or printed title Warranties and Bonds, with title of project, name, address, and telephone number of the Contractor and name of responsible principal.
- 3) Include table of contents, neatly typed, in sequence of table of contents of project

specifications with each item identified with number and title of specification section and name of product or work items.

- 4) Separate each warranty or bond with index tab sheets keyed to table of contents listing. Provide full information using separate typed sheets as necessary. List subcontractors, suppliers, and manufacturers with name, address, and telephone number of responsible principal.

b. Preparation of Submittals:

- 1) Obtain warranties and bonds executed in duplicate by responsible subcontractors, suppliers, and manufacturers within 10 days after completion of the applicable item of work. Except for items put into use with the Owner's permission, leave date of beginning of time of warranty until substantial completion date is determined.
- 2) Verify that documents are in proper form, contain full information, and are notarized, if required.
- 3) Certify that submittals are accurate and complete, if required by Owner.
- 4) Retain warranties and bonds until time specified for submittal.

c. Time of Warranty Submittals:

- 1) For equipment or component parts of equipment put into service during construction with the Owner's permission, submit documents within 10 days after acceptance.
- 2) Make other submittals within 10 days after substantial completion date before final application for payment.
- 3) For items of work when acceptance is delayed beyond substantial completion, submit within 10 days after acceptance, listing date of acceptance as beginning of warranty period.

- END -