MAKE-UP AIR HANDLING UNIT SCHEDULE

UNIT MARK	LOCATION	SERVICE	M^3/HR	ESP Pa	FAN					COOLING COIL											
					TYPE	DRIVE	TSP Pa	RPM	EFFICIENCY %	FACE VEL. M/S MAX.	ROWS/FP	CAP. KW	EAT °C DB	EAT °C WB	LAT °C DB	LAT °C WB	AIR △P Pa	L/S	EWT °C	LWT °C	WTR △P KPa
F1-CRMAU-R103	OFFICE L40	CLEANROOM	80,000	500	BACKWARD INCLINED	DIRECT	–	–	–	2.5	–	1479	35	31.8	19.0	19.0	–	44.2	12	20	<50

MAKE-UP AIR HANDLING UNIT SCHEDULE

DEHUMIDIFIER COIL											MOTOR				FILTER EFF. %			
FACE VEL. M/S MAX.	ROWS/FP	CAP. KW	EAT °C DB	EAT °C WB	LAT °C DB	LAT °C WB	AIR △P Pa	L/S	EWT °C	LWT °C	WTR △P KPa	ABSORBED POWER (KW)	POWER (kW)	VOLTAGE	TYPE	PRE-FILTER	FINAL	HEPA @0.3um	REMARKS
2.5	–	747	19.0	19.0	9.0	9.0	–	22.3	5	13	<50	–	66	3/460/60	TEFC	35	95	99.97	IE4 CLASS MOTOR, W/VARIABLE FREQUENCY DRIVE , FILTER SELECTION IS QUALIFIED TO MEET MERV 13

NOTE:

1. PROVIDE SUITABLE ANCHORAGE POINTS INSIDE THE MAU FOR FALL ARREST HARNESSES.
2. PIPE FM CERTIFIED INSULATION MATERIAL.
3. DUCT INSTALL FIRE DAMPER TO INHIBIT FIRE SPREAD.
4. PIPE AND DUCT THE GAP NEED TO BE FILLED WITH FIRE STOP.
5. MAU進氣口上方設置安全冠索供人員以A字梯上去後之安全勾掛

AMC AIR WASHER RECIRCULATION PUMP SCHEDULE

UNIT MARK	LOCATION	SERVICE	TYPE	Q'TY	SUCTION SIZE A	DISCHARGE SIZE A	FLOW L/S	HEAD M	RPM	MOTOR			FLUID	REMARKS
										POWER (KW)	VOLTAGE	TYPE		
F1-CRAP-R103A,B	OFFICE L40	L30	END SUCTION	2	–	–	6.5	53	–	8.6	3/460/60	TEFC	WATER	IE3 CLASS MOTOR

DRY COOLING COIL SCHEDULE

UNIT MARK	LOCATION	SERVICE	M^3/HR	FACE VEL. M/S	ROWS/FP, mm	EAT°C DB	LAT°C DB	AIR △ P Pa	L/S	EWT °C	LWT °C	WTR △P KPa	CAP. KW	COIL BANK				REMARKS
														FINNED SIZE, M L X W	Frame SIZE, M L X W	Q'TY	TOTAL CAP. KW	
DCC-01	FAB L20	CLEANROOM	36,210	2.4	3R/10F	25	18.0	<50	2.94	12.0	19.0	<50	88.3	2.55 X 1.638	2.72 X 1.71	214		垂直
DCC-02	FAB L20	CLEANROOM	57,024	2.4	3R/10F	25	18.0	<50	4.6	12.0	19.0	<50	133.5	3.95 X 1.638	4.23 X 1.72	21		垂直
DCC-08	FAB L20	CLEANROOM	45,663	2.4	3R/10F	25	18.0	<50	3.66	12.0	19.0	<50	107.6	3.95 X 1.333	4.23 X 1.42	7		垂直

FAN FILTER UNIT SCHEDULE

UNIT MARK	LOCATION	SERVICE	AIR VEL. M/S	NOMINAL SIZE mm	Q'TY	FAN				FILTER				SOUND PRESSURE LEVEL dBA	MOTOR			REMARKS
						IMPELLER	M^3/HR	TSP Pa	RPM	MEDIA	EFFICIENCY %	PARTICLE um	PRESSURE DROP Pa		KW	TYPE	VOLTAGE	
FFU-01	FAB LEVEL 30	CLEANROOM	0.45	1200X1200	3,975	CENTRIFUGAL, AEROFOIL	2332	180~270	–	FIBER GLASS	99.99995@MPPS	0.12	85±10%	<55	0.35	EC	1/277/60	

RAS HUMIDIFIER UNIT SCHEDULE

UNIT MARK	SYSTEM CAPCITY kg/hr	TYPE	WATER	PUMP STATION				PROPORTIONAL OUTPUT CONTROL MODULE	LOCATION	HUMIDIFIER	No. OF ZONE CONTROL	REMARKS
				POWER	PRESSURE MAX.	No. OF PUMP	MOTOR			kg/hr	ZONES	
HI FOG	1,500	HI FOG	RO	3 /460 /60	8.0 MPa	3 (2+1)	5 HP x 3 Sets,W/VFD	TIME PROPORTIONAL	FAB L30 (50K)	400 (TOTAL)	6	
									FAB L30 (200K)	1,500 (TOTAL)	26	

OWNER / DEVELOPER

micron

ARCHITECTURAL CONSULTANT

JJP ARCHITECTS & PLANNERS 潘冀聯合建築師

CIVIL & STRUCTURAL CONSULTANT

TEAM 群策工程股份有限公司

MECHANICAL & ELECTRICAL CONSULTANT & CONTRACTOR

uis United Integrated Services 漢唐集成股份有限公司

SUB-CONTRACTOR

PROJECT ADDRESS

KEY PLAN

REV	DATE	DESCRIPTION	ISSUED BY
A	2025/01/02	REVIEW Drawing	

Revisions

PROJECT TITLE

Micron Falcon A Project (200K)

PROJECT PHASE

Concept Design

DRAWING TITLE

EQUIPMENT SCHEDULE -
CLEANROOM HVAC SYSTEM
-
-

DESIGNED : ELLIS	DRAWN : ELLIS	CHECKED : C.S.HU	
DATE : 2024/11/20	JOB NO. :	SCALE : N.T.S	
DRAWING NO. DE_F1_ALL_B001_MB_MECH_6001-00			REV 0
		SHEET:	SIZE A1