

CENTRIFUGAL LIQUID CHILLER SCHEDULE																							
UNIT MARK	DESIGN DUTY TONS	EVAPORATOR						CONDENSER						HEAT RECOVERY						POWER		REMARKS	
		L/S	EWt °C	LWT °C	PASS	WTRΔP KPa	FOULING FACTOR	L/S	EWt °C	LWT °C	PASS	WTRΔP KPa	FOULING FACTOR	HEAT RECOVERY KW	L/S	EWt °C	LWT °C	PASS	WTRΔP KPa	FOULING FACTOR	CONSUMED POWER(KW)		VOLTAGE
F1-C3-12CH-001	2200	231	20	12	2	52	0.0176	356	32.0	38.0	2	58	0.044	-	-	-	-	-	-	-	1100	3/6600/60	
F1-C3-12CH-002	2200	231	20	12	2	52	0.0176	356	32.0	38.0	2	58	0.044	-	-	-	-	-	-	-	1100	3/6600/60	
F1-C3-12CH-003	2200	231	20	12	2	52	0.0176	356	32.0	38.0	2	58	0.044	-	-	-	-	-	-	-	1100	3/6600/60	
F1-C3-12CH-004	2200	231	20	12	2	52	0.0176	356	32.0	38.0	2	58	0.044	-	-	-	-	-	-	-	1100	3/6600/60	
F1-C3-12CH-005	2200	231	20	12	2	52	0.0176	356	32.0	38.0	2	58	0.044	-	-	-	-	-	-	-	1100	3/6600/60	
F1-C3-12CH-006	2200	231	20	12	2	52	0.0176	356	32.0	38.0	2	58	0.044	-	-	-	-	-	-	-	1100	3/6600/60	(STANDBY)

HVAC PUMP SCHEDULE														
UNIT MARK	SERVICE	TYPE	SUCTION SIZE IN	DISCHARGE SIZE IN	FLOW L/S	HEAD M	BHP	RPM	MOTOR			FLUID	REMARKS	
									HP	VOLTAGE	TYPE			
F1-C3-12CHP-001	CHILLED WATER PRODUCTION	IN-LINE	300	300	288	44	-	-	250	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CHP-002	CHILLED WATER PRODUCTION	IN-LINE	300	300	288	44	-	-	250	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CHP-003	CHILLED WATER PRODUCTION	IN-LINE	300	300	288	44	-	-	250	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CHP-004	CHILLED WATER PRODUCTION	IN-LINE	300	300	288	44	-	-	250	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CHP-005	CHILLED WATER PRODUCTION	IN-LINE	300	300	288	44	-	-	250	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CHP-006	CHILLED WATER PRODUCTION	IN-LINE	300	300	288	44	-	-	250	3/460/60	TEFC	WATER	W/VFD ,IE4 (STANDBY)	
F1-C3-12CWP-001	CONDENSER WATER	IN-LINE	350	350	356	28	-	-	200	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CWP-002	CONDENSER WATER	IN-LINE	350	350	356	28	-	-	200	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CWP-003	CONDENSER WATER	IN-LINE	350	350	356	28	-	-	200	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CWP-004	CONDENSER WATER	IN-LINE	350	350	356	28	-	-	200	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CWP-005	CONDENSER WATER	IN-LINE	350	350	356	28	-	-	200	3/460/60	TEFC	WATER	W/VFD ,IE4	
F1-C3-12CWP-006	CONDENSER WATER	IN-LINE	350	350	356	28	-	-	200	3/460/60	TEFC	WATER	W/VFD ,IE4 (STANDBY)	
F1-C2-CDA-CHWP-001	COMPRESSOR COOLING WATER	IN-LINE	-	-	70	15	-	-	30	3/380/60	TEFC	WATER	W/VFD ,IE4	
F1-C2-CDA-CHWP-002	COMPRESSOR COOLING WATER	IN-LINE	-	-	70	15	-	-	30	3/380/60	TEFC	WATER	W/VFD ,IE4 (STANDBY)	

Cooling Tower Cell Schedule										
Unit Mark	L/S	EWT °C	LWT °C	Air Temp °C WB	Motor			Type	Remarks	
					KW	Voltage	Type			
F1-C3-CT-001	514	38.4	32.4	29.4	95.2	3/460/60	TEFC	COUNTERFLOW	W/VFD,IE4 , (STANDBY)	
F1-C3-CT-002	514	38.4	32.4	29.4	95.2	3/460/60	TEFC	COUNTERFLOW	W/VFD,IE4	
F1-C3-CT-003	514	38.4	32.4	29.4	95.2	3/460/60	TEFC	COUNTERFLOW	W/VFD,IE4	
F1-C3-CT-004	514	38.4	32.4	29.4	95.2	3/460/60	TEFC	COUNTERFLOW	W/VFD,IE4	
F1-C3-CT-005	514	38.4	32.4	29.4	95.2	3/460/60	TEFC	COUNTERFLOW	W/VFD,IE4	

EXPANSION TANK SCHEDULE					
UNIT MARK	SERVICE	CAPACITY M ³	WORKING PRESS. BAR	TYPE	REMARKS
F1-C3-12ET-001	12°C CHILLED WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	
F1-C3-12ET-002	12°C CHILLED WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	

COOLING TOWER FILTRATION SYSTEM																		
UNIT MARK	SERVICE	FILTRATION TANK		DESIGN PRESSURE	TYPE	FILTR. EFF.	UNIT MARK	L/S	FILTRATION PUMP			REMARKS						
		Q'TY	MATERIAL						DIMENSION DxD (mm)	KPA	TYPE				HEAD M	MOTOR		
																KW	VOLTAGE	TYPE
F1-C3-FS-R101	CONDENSER WATER FILTRATION	1	CARBON STEEL	Ø2438 x 2881	350	SAND	90% @ 5um	F1-C3-FSP-R101	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4			
F1-C3-FS-R102	CONDENSER WATER FILTRATION	1	CARBON STEEL	Ø2438 x 2881	350	SAND	90% @ 5um	F1-C3-FSP-R102	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4			
F1-C3-FS-R103	CONDENSER WATER FILTRATION	1	CARBON STEEL	Ø2438 x 2881	350	SAND	90% @ 5um	F1-C3-FSP-R103	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4 (STANDBY)			

SERVER & CPU ROOM AIR HANDLING UNIT SCHEDULE																																	
UNIT MARK	LOCATION	SERVICE	CMH	E.S.P Pa	FAN			COOLING COIL										REFEAT			HUMIDIFIER		MOTOR			FILTER EFF. %		REMARKS					
					TYPE	BHP	RPM	FACE VEL M/S MAX.	RWS/PPF	TAIL CAP. KW	SEN CAP. KW	DB	EAT °C	WB	DB	WB	AIR Δ P Pa	L/S	FWT °C	LWT °C	WTR Δ P KPa	HEAT CAP. KW	HEATER KW	RUNNING AMPERE	EAT °C	DB	LAT °C		TOTAL CAP. kg/hr	POWER KW	HP	POWER SOURCE	TYPE
F1-C3-CAH-001	CUB3 L20	SERVER ROOM (机房)	20100	250	BACKWARD INLINED	-	-	2.6	-	107	87	25	17.8	12.0	12.0	-	4.3	12	20	-	24	6x4	115	10.0	13.5	9	7.2	10	3/460/60	ODP	35	-	
F1-C3-CAH-002	CUB3 L20	SERVER ROOM (机房)	20100	250	BACKWARD INLINED	-	-	2.6	-	107	87	25	17.8	12.0	12.0	-	4.3	12	20	-	24	6x4	115	10.0	13.5	9	7.2	10	3/460/60	ODP	35	-	
F1-C3-CAH-003	CUB3 L20	SERVER ROOM (机房)	20100	250	BACKWARD INLINED	-	-	2.6	-	107	87	25	17.8	12.0	12.0	-	4.3	12	20	-	24	6x4	115	10.0	13.5	9	7.2	10	3/460/60	ODP	35	-	STANDBY

MAKE UP AIR HANDLING UNIT SCHEDULE																						
UNIT MARK	LOCATION	SERVICE	FAN					COOLING COIL								MOTOR			FILTER EFF. %		REMARKS	
			TYPE	CMH	ESP(pa)	DRIVE TYPE	RPM	FACE VEL. M/S MAX.	CAP (KW)	EAT°C		LAT°C		EWT °C	LWT °C	L/S	HP	POWER SOURCE	TYPE	PRE		FINAL
										DB	WB	DB	WB									
F1-C3-MAU-001	CUB3 L20	CUB	BACKWARD CURVED	13,000	500	DIRECT	-	2.6	167	35.0	29.4	20.0	20.0	12.0	20.0	5	15	3/460/60	TEFC	35	85	W/VFD JE4 FILTER MERV 13 附負離子機-GPS-FC48-AC

UNIT MARK	LOCATION	SERVICE	CMH	M/S	FAN		WHEEL TYPE	DRIVE	ESP Pa	THRUST N	SOUND PRESS. 4.5° AT 10m dBA	SOUND POWER dBA	BHP	MOTOR			REMARK
					TYPE	RPM								KW	VOLTAGE	TYPE	
F1-C3-SF-1001	CUB3 L10	GIS ROOM	8000	-	WALL MOUNTED	-	PROPELLER	DIRECT	62.5	-	-	-	-	0.74	3/460/60	TEFC	MOTOR IE 4
F1-C3-SF-1002	CUB3 L10	DIESEL STORAGE TANK	3500	-	INLINE FAN	-	BACKWARD INCLINED	BELT	500	-	-	-	-	1.1	3/460/60	TEFC	MOTOR IE 4 使用 防爆型馬達
F1-C3-SF-1003	CUB3 L10	DIESEL DAILY TANK	3500	-	INLINE FAN	-	BACKWARD INCLINED	BELT	500	-	-	-	-	1.1	3/460/60	TEFC	MOTOR IE 4 使用 防爆型馬達
F1-C3-SF-1004	CUB3 L30	DIESEL DAILY TANK	3500	-	INLINE FAN	-	BACKWARD INCLINED	BELT	500	-	-	-	-	1.1	3/460/60	TEFC	MOTOR IE 4 使用 防爆型馬達

micon

ARCHITECTURAL CONSULTANT

JJP ARCHITECTS & PLANNERS 潘冀聯合建築師

CIVIL & STRUCTURAL CONSULTANT
TEAM 群策工程股份有限公司

MECHANICAL & ELECTRICAL CONSULTANT & CONTRACTOR

uis 漢唐集成股份有限公司

SUB-CONTRACTOR

PROJECT ADDRESS

KEY PLAN

A	2025/01/02	REVIEW Drawing	
REV	DATE	DESCRIPTION	ISSUED BY
		Revisions	

PROJECT TITLE
Micron Falcon A Project (200K)

PROJECT PHASE
Concept Design

DRAWING TITLE
EQUIPMENT SCHEDULE
- GENERAL HVAC SYSTEM
(1)

DESIGNED-JACK CHANG	DRAWN: JACK CHANG	CHECKED: C.S.HU
DATE : 2024/11/20	JOB NO.:	SCALE :

DRAWING NO. DE_F1_ALL_B001_M_MECH_6001-00	SHEET: 	REV 0 SIZE A
--	------------	-----------------------