PCW PUMP SCHEDULE

UNIT MARK	LOCATION	SERVICE	TYPE	FLOW RATE m3/h	HEAD m	MATERIAL			SUCTION NOZZLE	DISCHARGE NOZZLE	EFFICIENCY %	MOTOR			REMARKS
						VOLUTE CASING	CASING COVER	IMPELLER				KW	VOLTAGE	TYPE	
FAL-PCW-P-101	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (50K)
FAL-PCW-P-102	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (50K)
FAL-PCW-P-103	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (50K)
FAL-PCW-P-104	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (200K)
FAL-PCW-P-105	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (200K)
FAL-PCW-P-106	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (200K)(STANDBY)
FAL-PCW-P-107	FAB L30	L20 15.5°C SYSTEM	HORIZONTAL,END-SUCTION PUMP	410	85	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	STAINLESS STEEL 1.4408	DN200	DN150	80	152	3/480/60	TEFC	MOTOR W/VFD & "IE4"; (200K) (FUTURE)

PLATE TYPE HEAT EXCHANGER

UNIT MARK	LOCATION	SERVICE	FLUID	HOT SIDE				COLD SIDE				HEAT EXCHANGED KW	DESIGN PRESSURE Barg	PLATE MATERIAL	PLATE SEALING MATERIAL	REMARKS
				FLOW RATE(m3/h)	INLET TEMP.(°C)	OUTLET TEMP.(°C)	PRESSURE DROP(kPa)	FLOW RATE(m3/h)	INLET TEMP.(°C)	OUTLET TEMP.(°C)	PRESSURE DROP(kPa)					
FAL-PCW-HEX-101	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(50K)
FAL-PCW-HEX-102	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(50K)
FAL-PCW-HEX-103	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(50K)
FAL-PCW-HEX-104	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(200K)
FAL-PCW-HEX-105	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(200K)
FAL-PCW-HEX-106	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(200K) (STANDBY)
FAL-PCW-HEX-107	FAB L30	L20 15.5°C SYSTEM	WATER	410	20.0	15.5	< 50	369	12.0	17.0	< 50	2135	10	SUS 304	EPDM	(200K) (FUTURE)

LIQUID FILTER SCHEDULE

UNIT MARK	LOCATION	SERVICE	FLOW RATE m3/h	RATING um	OPERATING PRESSURE(Barg)	HOUSING MATERIAL	FILTER MATERIAL	INITIAL DIFF. PRESS. kPa(MAX)	REMARKS
FAL-PCW-FLT-101	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(50K)
FAL-PCW-FLT-102	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(50K)
FAL-PCW-FLT-103	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(50K)
FAL-PCW-FLT-104	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(200K)
FAL-PCW-FLT-105	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(200K)
FAL-PCW-FLT-106	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(200K)(STANDBY)
FAL-PCW-FLT-107	FAB L30	L20 15.5°C SYSTEM	410	< 40um	10	SUS 304	POLYPROPYLENE	34	(200K) (FUTURE)

WATER TANK SCHEDULE

UNIT MARK	LOCATION	SERVICE	CAPACITY M3	MATERIAL		ELECTRICAL DATA			REMARKS
				SHELL	BLADDER	KW	VOLTAGE	CLASS	
FAL-PCW-ET-101	FAB L30	L20 15.5°C SYSTEM	25	STAINLESS STEEL	--				(50K)

OWNER / DEVELOPER

micron

ARCHITECTURAL CONSULTANT

JJP ARCHITECTS & PLANNERS 潘冀聯合建築師

CIVIL & STRUCTURAL CONSULTANT

TEAM 群策工程股份有限公司

MECHANICAL & ELECTRICAL CONSULTANT & CONTRACTOR

uis United Integrated Services 漢唐集成股份有限公司

SUB-CONTRACTOR

PROJECT ADDRESS

KEY PLAN

REV	DATE	DESCRIPTION	ISSUED BY
A	2025/02/14	REVIEW Drawing	

Revisions

PROJECT TITLE

Micron MMTN Project (200K)

PROJECT PHASE

Concept Design

DRAWING TITLE

EQUIPMENT SCHEDULE - PCW SYSTEM

-

DESIGNED : CHEN	DRAWN : CHEN	CHECKED : CHUNGSIR	
DATE : 2025/2/14	JOB NO. :	SCALE : N.T.S.	
DRAWING NO. DE_MMTN_ALL_B0001_D_WPCW_0001-00			REV A
		SHEET:	SIZE A1