

MAKE-UP AIR HANDLING UNIT SCHEDULE																					
UNIT MARK	LOCATION	SERVICE	M ³ /HR	ESP Pa	FAN				COOLING COIL												
					TYPE	DRIVE	TSP Pa	RPM	EFFICIENCY %	FACE VEL M/S MAX.	ROWS/FP	CAP. KW	EAT °C				AIR ΔP Pa	L/S	EWI °C	LWT °C	WTR ΔP KPa
F1-CRMAU-R103	OFFICE L40	CLEANROOM	80,000	500	BACKWARD INCLINED	DIRECT	-	-	-	2.5	-	1479	35	31.8	19.0	19.0	-	44.2	12	20	<50

MAKE-UP AIR HANDLING UNIT SCHEDULE																			
FACE VEL. M/S MAX.	ROWS/FP	CAP. KW	DEHUMIDIFIER COIL				AIR Δ P Pa	L/S	EWT °C	LWT °C	WTR Δ P kPa	ABSORBED POWER (kW)	MOTOR POWER (kW)	VOLTAGE	TYPE	FILTER EFF. %			REMARKS
			EAT °C	DB	WB	LA T °C										WB	PRE-FILTER	FINAL	
2.5	—	747	19.0	19.0	9.0	9.0	22.3	5	13	<50	—	66	3/460/60	TEFC	35	95	99.97	IE4 CLASS MOTOR, W/VARIABLE FREQUENCY DRIVE , FILTER SELECTION IS QUALIFIED TO MEET MERV 13	

NOTE:

1. PROVIDE SUITABLE ANCHORAGE POINTS INSIDE THE MAU FOR FALL ARREST HARNESSES.
2. PIPE FM CERTIFIED INSULATION MATERIAL.
3. DUCT INSTALL FIRE DAMPER TO INHIBIT FIRE SPREAD.
4. PIPE AND DUCT THE GAP NEED TO BE FILLED WITH FIRE STOP.
5. MAU 進氣口上方設置安全網索供人員以入字樣上表之安全帶扣掛

AMC AIR WASHER RECIRCULATION PUMP SCHEDULE														
UNIT MARK	LOCATION	SERVICE	TYPE	Q'TY	SUCTION SIZE A	DISCHARGE SIZE A	FLOW L/S	HEAD M	RPM	MOTOR			FLUID	REMARKS
										POWER (KW)	VOLTAGE	TYPE		
F1-CRAP-R103A,B	OFFICE L40	L30	END SUCTION	2	—	—	6.5	5.3	—	8.6	3/460/60	TEFC	WATER	IE3 CLASS MOTOR

DRY COOLING COIL SCHEDULE																		
UNIT MARK	LOCATION	SERVICE	M ³ /HR	FACE VEL. M/S	ROWS/FP, mm	EAT ^o C DB	LATC DB	AIR Δ P ₀	P	L/S	EWT °C	LWT °C	WTR ΔP KPa	CAP. KW	COIL BANK			REMARKS
															FINNED SIZE, M L X W	Frame SIZE, M L X W	Q'TY	
DCC-01	FAB L20	CLEANROOM	36,210	2.4	3R/10F	25	18.0	<50	2.94	12.0	19.0	<50	88.3	2.55 X 1.638	2.72 X 1.71	214		廢氣
DCC-02	FAB L20	CLEANROOM	57,024	2.4	3R/10F	25	18.0	<50	4.6	12.0	19.0	<50	133.5	3.95 X 1.638	4.23 X 1.72	21		廢氣
DCC-08	FAB L20	CLEANROOM	45,663	2.4	3R/10F	25	18.0	<50	3.66	12.0	19.0	<50	107.6	3.95 X 1.333	4.23 X 1.42	7		廢氣

FAN FILTER UNIT SCHEDULE																		
UNIT MARK	LOCATION	SERVICE	AIR VEL. M/S	NOMINAL SIZE mm	Q'Ty	FAN				FILTER				SOUND PRESSURE LEVEL dBA	MOTOR			REMARKS
						IMPELLER	M ³ /HR	TSP Pa	RPM	MEDIA	EFFICIENCY %	PARTICLE um	PRESSURE DROP Pa		KW	TYPE	VOLTAGE	
FFU-01	FAB LEVEL 30	CLEANROOM	0.45	1200X1200	3,975	CENTRIFUGAL, AEROFOIL	2332	180~270	-	FIBER GLASS	99.99995@MPPS	0.12	85±10%	<55	0.35	EC	1/277/60	

RAS HUMIDIFIER UNIT SCHEDULE												
UNIT MARK	SYSTEM CAPACITY kg/hr	TYPE	WATER	PUMP STATION				PROPORTIONAL OUTPUT CONTROL MODULE	LOCATION	HUMIDIFIER kg/hr	No. OF ZONE CONTROL ZONES	REMARKS
				POWER	PRESSURE MAX.	No. OF PUMP	MOTOR					
HI FOG	1,500	HI FOG	RO	3 /460 /60	8.0 MPa	3 (2+1)	5 HP x 3 Sets,W/VFD	TIME PROPORTIONAL	FAB L30 (50k)	400 (TOTAL)	6	
									FAB L30 (200K)	1,500 (TOTAL)	26	

[illegible]