

1

2

3

4

5

6

7

8

9

10

11

12

13

14

A

B

C

D

E

F

G

H

I

J

COOLING TOWER FILTRATION SYSTEM

UNIT MARK	SERVICE	FILTRATION TANK		DESIGN PRESSURE	FILTER		UNIT MARK	L/S	FILTRATION PUMP	HEAD	MOTOR			REMARKS	
		Q'TY	MATERIAL		DIMENSION D×H (mm)	KPA					TYPE	EFF.	KW		VOLTAGE
22P1-CR1P-CDW3-FS01	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1P-CDW3-P01	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1P-CDW3-FS02	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1P-CDW3-P02	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1P-CDW3-FS03	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1P-CDW3-P03	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1Q-CDW3-FS04	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1Q-CDW3-P04	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1Q-CDW3-FS05	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1Q-CDW3-P05	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1Q-CDW3-FS06	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1Q-CDW3-P06	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1Q-CDW3-FS07	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1Q-CDW3-P07	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(STAGE 1)
22P1-CR1Q-CDW3-FS08	CONDENSER WATER FILTRATION	1	CARBON STEEL	ø2438 x 2881	350	SAND	90% @ 5um	22P1-CR1Q-CDW3-P08	63.5	IN-LINE	24.4	22	3/460/60	TEFC	IE4,(FUTURE)

EXPANSION TANK SCHEDULE

UNIT MARK	SERVICE	CAPACITY M³	WORKING PRESS. BAR	TYPE	REMARKS
22P1-C10Q-5CH3-ET01	5°C CHILLED WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	(STAGE 1)
22P1-C10Q-5CH3-ET02	5°C CHILLED WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	(STAGE 1)
22P1-C10Q-12CH3-ET01	12°C CHILLED WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	(STAGE 1)
22P1-C10Q-12CH3-ET02	12°C CHILLED WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	(STAGE 1)
22P1-C10Q-35WW3-ET01	35°C WARM WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	(STAGE 1)
22P1-C10Q-35WW3-ET02	35°C WARM WATER SYSTEM	2.0	8.6	VERTICAL, PRECHARGED BLADDER-TYPE	(STAGE 1)

PLATE TYPE HEAT EXCHANGER SCHEDULE

UNIT MARK	SERVICE	CAPACITY KW	COLD SIDE					HOT SIDE					REMARKS
			EWI °C	LWT °C	L/S	WTR ΔP KPa	FLUID	EWI °C	LWT °C	L/S	WTR ΔP KPa	FLUID	
22P1-C10P-35WW3-HX07	35°C WARM WATER SYSTEM	9582	12	21.9	223.7	<50	WATER	42	32	223.7	<50	WATER	(STANDBY) (STAGE 1)
22P1-C10P-35WW3-HX08	35°C WARM WATER SYSTEM	9582	12	21.9	223.7	<50	WATER	42	32	223.7	<50	WATER	(FUTURE)

KEY PLANT

U (N) V

Building Code

A: Office

F: FAB

H: HPM

C: CUP

G: Gas Yard & BSGS

S: Supporting

N: ASC

W: Warehouse

1

2

3

4

5

6

7

8

9

10

11

12

13

14

A

B

C

D

E

F

G

H

I

J

1

2

3

4

5

6

7

8

9

10

11

12

13

14

A

B

C

D

E

F

G

H

I

J

VER.

DATE

修正者

修正

REVISION

tsmc

台灣積體電路製造股份有限公司

Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED

DATE

ACCEPTANCE REVIEWED

DATE

CONTRACTOR

uis

漢唐集成股份有限公司

United Integrated Services

DRAWN

TCM

DATE

2024/02/27

RECHECKED

Steven Yu

DATE

2024/02/27

DESIGNED

TCM

DATE

2024/02/27

APPROVED

JOSEPH LEE

DATE

2024/02/27

TITLE

MECHANICAL SYSTEM

EQUIPMENT SCHEDULE

(3)

-

PROJECT

FAB22 Phase 1 PROJECT

PACKAGE NAME

MEP SYSTEM

DRAWING NAME

F22P1-M-1-C-03

SCALE

NOT TO SCALE

UNIT

mm

FILE NAME

F22P1-M-1-C-03

Rev.

1

2

3

4

5

6

7

8

9

10

11

12

13

14

1

2

3

4

5

6

7

8

9

10

11

12

13

14

Serial number: 202501201326-14437217

出圖日期: 2024/02/27

	1	2	3	4	5	6	7	8	9	10	11	12	13	14										
A	MAKE-UP AIR HANDLING UNIT SCHEDULE																							
	UNIT MARK	LOCATION	SERVICE	QTY	FAN				COOLING COIL							MOTOR			FILTER EFF.%		REMARKS			
					TYPE	CMH	ESP(pa)	RPM	FACE VEL. M/S MAX.	CAP.(KW)	EAT °C		LAT °C		EWT °C	LWT °C	L/S	HP	POWER SOURCE	TYPE		PRE.	FINAL	
	22P1-C20Q-MAU3-AH01	CUP L20	H2 PURIFIER & Solvent Bottle	1	BACKWARD CURVED	45400	500	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	30	3/460/60	TEFC	35	85	(出風,外氣風門開關)(濾網應用 MERV 13) W/VFD,IE3	
	22P1-C20Q-MAU3-AH02	CUP L20	H2 PURIFIER & Solvent Bottle	1	BACKWARD CURVED	45400	500	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	30	3/460/60	TEFC	35	85	(出風,外氣風門開關)(濾網應用 MERV 13) W/VFD,IE3 (STANDBY)	
B	22P1-C30P-MAU3-AH03	CUP L30	N2 PURIFIER & CCD,ELECTRIC ROOM	1	BACKWARD CURVED	45400	500	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	30	3/460/60	TEFC	35	85	(出風,外氣風門開關)(濾網應用 MERV 13) W/VFD,IE3	
	22P1-C30P-MAU3-AH04	CUP L30	N2 PURIFIER & CCD,ELECTRIC ROOM	1	BACKWARD CURVED	45400	500	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	30	3/460/60	TEFC	35	85	(出風,外氣風門開關)(濾網應用 MERV 13) W/VFD,IE3 (STANDBY)	
	AIR HANDLING UNIT SCHEDULE																							
	UNIT MARK	LOCATION	SERVICE	QTY	FAN				COOLING COIL							MOTOR			FILTER EFF.%		CHEMICAL	REMARKS		
					TYPE	CMH	ESP(pa)	RPM	FACE VEL. M/S MAX.	CAP.(KW)		EAT °C		LAT °C		EWT °C	LWT °C	L/S	HP	POWER SOURCE	TYPE		PRE.	FINAL
22P1-C30Q-AHU3-AH01	CUP L30	I/O ROOM,FMCS,PA,COSD	1	BACKWARD CURVED	25000	500	-	2.6	245	132	27.8	21.9	12.5	12.5	5.0	13.0	7.2	20	3/460/60	TEFC	35	85	V-type化濾棉	附蓋/出風,外氣風門開關,(MERV 13) W/VFD,IE3
22P1-C30Q-AHU3-AH02	CUP L30	I/O ROOM,FMCS,PA,COSD	1	BACKWARD CURVED	25000	500	-	2.6	245	132	27.8	21.9	12.5	12.5	5.0	13.0	7.2	20	3/460/60	TEFC	35	85	V-type化濾棉	附蓋/出風,外氣風門開關,(MERV 13) W/VFD,IE3 (STANDBY)
C	EXHAUST FAN SCHEDULE																							
	UNIT MARK	LOCATION	SERVICE	QTY	FAN					MOTOR			REMARKS											
					TYPE	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	KW		POWER SOURCE	TYPE									
	22P1-C10P-EF3-F01	CUP L10	CABLE ROOM	1	INLINE FAN	5400	250	FORWARD CURVED	-	BELT	-	2.2	3/460/60	-	MOTOR: IE4;室內落地型									
	22P1-C10Q-EF3-F02	CUP L10	CABLE ROOM	1	INLINE FAN	5400	250	FORWARD CURVED	-	BELT	-	2.2	3/460/60	-	MOTOR: IE4;室內落地型									
D	22P1-C10P-EF3-F04	CUP L10	加藥室	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-										
	22P1-C10Q-EF3-F05	CUP L10	DIESEL PUMP/DAILY TANK	1	INLINE FAN	4500	250	FORWARD CURVED	-	BELT	-	1.49	3/460/60	-	MOTOR: IE4;室內吊掛型									
	22P1-C10Q-EF3-F06	CUP L10	CHILLER ROOM	1	AXIAL FAN	30000	500	AXIAL	-	BELT	-	11	3/460/60	-	MOTOR: IE4;室內吊掛型									
	22P1-C10Q-EF3-F07	CUP L10	CHILLER ROOM	1	AXIAL FAN	30000	500	AXIAL	-	BELT	-	11	3/460/60	-	MOTOR: IE4;室內吊掛型									
	22P1-C20P-EF3-F08	CUP L20	FILTER PRESS	1	WALL MOUNTED	8000	62.5	PROPELLER	-	DIRECT	-	0.75	3/460/60	-										
E	22P1-C20P-EF3-F09	CUP L20	FILTER PRESS	1	WALL MOUNTED	8000	62.5	PROPELLER	-	DIRECT	-	0.75	3/460/60	-										
	22P1-CR1P-EF3-F11	CUP LR1	DAILY TANK	1	INLINE FAN	2500	500	BACKWARD INCLINED	-	BELT	-	0.75	3/460/60	-	MOTOR: IE4;戶外落地型									
	22P1-CR1Q-EF3-F12	CUP LR1	DAILY TANK	1	INLINE FAN	5000	500	BACKWARD INCLINED	-	BELT	-	1.5	3/460/60	-	MOTOR: IE4;戶外落地型									
	22P1-CR1Q-EF3-F15	CUP LR1	廁所/茶水間 & INERGENT/CO2 BOTILE ROOM	1	INLINE FAN	16000	500	BACKWARD INCLINED	-	BELT	-	7.5	3/460/60	-	MOTOR: IE4;戶外落地型									
	22P1-CR2Q-EF3-F16	CUP LR2	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-										
F	SUPPLY FAN SCHEDULE																							
	UNIT	LOCATION	SERVICE	QTY	FAN					MOTOR			REMARKS											
					TYPE	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	KW		POWER SOURCE	TYPE									
	22P1-C40P-SF3-F01	CUP L40	DAILY TANK	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-										
	22P1-C40Q-SF3-F02	CUP L40	DAILY TANK	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-										
G	22P1-C40Q-SF3-F03	CUP L40	DAILY TANK	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-										
	22P1-C10Q-SF3-F04	CUP L10	DAILY TANK	1	WALL MOUNTED	800	62.5	PROPELLER	-	DIRECT	-	0.06	1/208/60	-										
	DE-SMOKE EXHAUST FAN SCHEDULE																							
	UNIT MARK	LOCATION	SERVICE	QTY	FAN					MOTOR			REMARKS											
					TYPE	CLASS	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP		KW	POWER SOURCE	TYPE								
22P1-CR1Q-DES3-F01	CUP LR1	OFFICE & FMCS	1	DESMOKE TUBULAR CENTRIFUGAL	1	30000	1000	AIRFOIL CENTRIFUGAL WHEEL	-	BELT	-	19	3/460/60	TEFC	室外落地型									
H	CO2 EXHAUST FAN SCHEDULE																							
	UNIT MARK	LOCATION	SERVICE	QTY	FAN					MOTOR			REMARKS											
					TYPE	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	KW		POWER SOURCE	TYPE									
	22P1-CR1P-CEX3-F01	CUP LR1	ELECTRICAL/CCD ROOM	1	INLINE FAN	22000	500	BACKWARD INCLINED	-	BELT	-	7.5	3/460/60	TEFC	室外落地型 (上蓋斜出)									
	I	FAN COIL UNIT SCHEDULE																						
UNIT MARK		QTY	AIR FLOW CMH	ESP(pa)	COOLING COIL								HEATING COIL			MOTOR			REMARKS					
					TOTAL KW	SENSIBLE KW	EAT °C		LAT °C		L/S	EWT °C	LWT °C	CAP. KW	EAT °C DB	L/S	EWT °C	LWT °C		WATTS	POWER SOURCE	TYPE		
					DB	WB	DB	WB	DB	WB														
④		-	684	50	4.33	2.63	25	20	-	-	0.21	5	10	-	-	-	-	-	95	1/208/60	-	吊掛隱藏式小型送風機 (附溫度控制器及控制面板) CEILING RECESSED TYPE		
⑥	-	1044	50	5.76	3.54	25	20	-	-	0.28	5	10	-	-	-	-	-	142	1/208/60	-	吊掛隱藏式小型送風機 (附溫度控制器及控制面板) CEILING RECESSED TYPE			
J	⑧	1	1332	50	8.01	4.83	25	20	-	-	0.39	5	10	-	-	-	-	-	166	1/208/60	-	吊掛隱藏式小型送風機 (附溫度控制器及控制面板) CEILING RECESSED TYPE		
	⑩	-	1728	50	9.58	5.87	25	20	-	-	0.46	5	10	-	-	-	-	-	228	1/208/60	-	吊掛隱藏式小型送風機 (附溫度控制器及控制面板) CEILING RECESSED TYPE		
	⑫	16	2052	50	10.92	6.82	25	20	-	-	0.53	5	10	-	-	-	-	-	285	1/208/60	-	吊掛隱藏式小型送風機 (附溫度控制器及控制面板) CEILING RECESSED TYPE		
	△	-	684	50	4.33	2.63	25	20	-	-	0.21	5	10	-	-	-	-	-	95	1/208/60	-	吊掛露明式小型送風機 (附溫度控制器及控制面板)		
	△	2	1044	50	5.76	3.54	25	20	-	-	0.28	5	10	-	-	-	-	-	142	1/208/60	-	吊掛露明式小型送風機 (附溫度控制器及控制面板)		
△	-	1332	50	8.01	4.83	25	20	-	-	0.39	5	10	-	-	-	-	-	166	1/208/60	-	吊掛露明式小型送風機 (附溫度控制器及控制面板)			
△	-	1728	50	9.58	5.87	25	20	-	-	0.46	5	10	-	-	-	-	-	228	1/208/60	-	吊掛露明式小型送風機 (附溫度控制器及控制面板)			
△	4	2052	50	10.92	6.82	25	20	-	-	0.53	5	10	-	-	-	-	-	285	1/208/60	-	吊掛露明式小型送風機 (附溫度控制器及控制面板)			
	1	2	3	4	5	6	7	8	9	10	11	12	13	14										

	1	2	3	4	5	6	7	8	9	10	11	12	13	14							
A	PACKAGED AIR HANDLING UNIT SCHEDULE																				
	UNIT MARK	LOCATION	SERVICE	QTY	FAN				COOLING COIL						MOTOR			FILTER EFF.%		REMARKS	
					TYPE	CMH	ESP(pa)	RPM	CAP.(KW)		EATC		WB	EWT	LWT	L/S	HP	POWER SOURCE	TYPE		PRE.
B	22P1-C10P-PAH3-AH01	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10P-PAH3-AH02	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10P-PAH3-AH03	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10P-PAH3-AH04	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10Q-PAH3-AH05	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10Q-PAH3-AH06	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10Q-PAH3-AH07	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10Q-PAH3-AH08	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10Q-PAH3-AH09	CUP L10	CHILLER ROOM	1	FORWARD CURVED	20100	-	-	199	129	29.0	20.7	5.0	13.3	5.85	7.5	3/460/60	-	35	-	MOTOR: IE4; 上直吹型
	22P1-C10P-PAH3-AH10	CUP L10	CDA ROOM	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C10P-PAH3-AH11	CUP L10	CDA ROOM	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C10P-PAH3-AH12	CUP L10	CDA ROOM	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20P-PAH3-AH13	CUP L20	CDA ROOM	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20P-PAH3-AH14	CUP L20	CDA ROOM	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20Q-PAH3-AH15	CUP L20	PA ROOM	1	FORWARD CURVED	13800	350	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4;進,出風皆須銜接風管(側拉濾網)
	22P1-C20Q-PAH3-AH16	CUP L20	PA ROOM	1	FORWARD CURVED	13800	350	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4;進,出風皆須銜接風管(側拉濾網)
	22P1-C30Q-PAH3-AH17	CUP L30	I/O ROOM	1	FORWARD CURVED	13800	350	-	138	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4;進,出風皆須銜接風管(側拉濾網)
	22P1-C30Q-PAH3-AH18	CUP L30	I/O ROOM	1	FORWARD CURVED	13800	350	-	138	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4;進,出風皆須銜接風管(側拉濾網)
D	ELECTRICAL/UPS ROOM PACKAGED AIR HANDLING UNIT SCHEDULE																				
	UNIT MARK	LOCATION	SERVICE	QTY	FAN				COOLING COIL						MOTOR			FILTER EFF.%		REMARKS	
					TYPE	CMH	ESP(pa)	RPM	CAP.(KW)		EATC		WB	EWT	LWT	L/S	HP	POWER SOURCE	TYPE		PRE.
E	22P1-C20Q-PAH3-AH22~23	CUP L20	C20P1	2	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20Q-PAH3-AH24	CUP L20	C20P2	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20Q-PAH3-AH25	CUP L20	C20P2	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR: IE4; (FUTURE)
	22P1-C20P-PAH3-AH26~27	CUP L20	C20P2	2	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20P-PAH3-AH28~30	CUP L20	C20P1	3	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C20P-PAH3-AH31	CUP L20	C20P1	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4; (FUTURE)
	22P1-C30Q-PAH3-AH32~34	CUP L30	C30P1	3	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C30Q-PAH3-AH35	CUP L30	C30P1	1	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR: IE4; (FUTURE)
	22P1-C30P-PAH3-AH36~37	CUP L30	C30P2	3	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C30Q-PAH3-AH38	CUP L30	C30P2	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4; (FUTURE)
	22P1-C30Q-PAH3-AH39	CUP L30	C30P2	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR: IE4; (FUTURE)
	22P1-C40Q-PAH3-AH48	CUP L40	C40P1	1	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR: IE4;
	22P1-C40Q-PAH3-AH49	CUP L40	C40P1	1	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR: IE4; (FUTURE)
	22P1-C40P-PAH3-AH50~51	CUP L40	C40P1	2	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR: IE4;
	G	TERMINAL UNIT SCHEDULE																			
		UNIT MARK	SERVICE	TYPE	AIR FLOW CMH		INLET SIZE mm	CONTROL		RADIATED SOUND POWER, dB (NOTE 1)							QTY	REMARKS			
					MAX.	MIN.		TYPE	FUNCTION	VOLTAGE	125Hz	250Hz	500Hz	1000Hz	2000Hz	4000Hz					
	H	TVB-4	GENERAL OFFICE	SINGLE DUCT	360	36	100	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.		
TVB-5		GENERAL OFFICE	SINGLE DUCT	594	72	125	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
TVB-6		GENERAL OFFICE	SINGLE DUCT	774	90	150	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
TVB-7		GENERAL OFFICE	SINGLE DUCT	1080	108	175	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
TVB-8		GENERAL OFFICE	SINGLE DUCT	1368	144	200	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
TVB-10		GENERAL OFFICE	SINGLE DUCT	2304	234	250	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
I	TVB-12	GENERAL OFFICE	SINGLE DUCT	3600	360	300	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
	TVB-14	GENERAL OFFICE	SINGLE DUCT	5400	540	350	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
	TVB-16	GENERAL OFFICE	SINGLE DUCT	6804	684	400	TEMPERATURE-INDEPENDENT ANALOG ELECTRONIC	MODULATION	-	-	-	-	-	-	-	-	-	THE RADIATED SOUND POWER SHOWN HERE IS BASED ON THE 1.5 x MINIMUM STATIC PRESSURE.			
J	1	2	3	4	5	6	7	8	9	10	11	12	13	14							

	1	2	3	4	5	6	7	8	9	10	11	12	13	14							
PACKAGED AIR HANDLING UNIT SCHEDULE																					
	UNIT MARK	LOCATION	SERVICE	QTY	FAN				COOLING COIL					MOTOR		FILTER EFF.%		REMARKS			
					TYPE	CMH	ESP(pa)	RPM	CAP.(KW)		DB	EAT°C	WB	EWT °C	LWT °C	L/S	HP		POWER SOURCE	TYPE	PRE.
A	22P1-FB1B-PAH1-AH21	22P1A FAB LB1	FB1B	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1B-PAH1-AH22	22P1A FAB LB1	FB1B	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1B-PAH1-AH23	22P1A FAB LB1	FB1B	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-FB1B-PAH1-AH24	22P1A FAB LB1	FB1B	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4
B	22P1-FB1D-PAH1-AH25	22P1A FAB LB1	FB1D	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1D-PAH1-AH26	22P1A FAB LB1	FB1D	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-FB1D-PAH1-AH27	22P1A FAB LB1	FB1D	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1D-PAH1-AH28	22P1A FAB LB1	FB1D	1	FORWARD CURVED	13800	250	-	136	87	29.0	20.7	5.0	13.3	3.9	7.5	3/460/60	-	35	-	MOTOR:IE4
C	22P1-FB1D-PAH1-AH29	22P1A FAB LB1	FB1D1	1	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1D-PAH1-AH30	22P1A FAB LB1	FB1D1	1	FORWARD CURVED	11000	250	-	108	70	29.0	20.7	5.0	13.3	3.1	5	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10A-PAH1-AH31	22P1A FAB L10	F10A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10A-PAH1-AH32	22P1A FAB L10	F10A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
D	22P1-F10A-PAH1-AH33	22P1A FAB L10	F10A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10A-PAH1-AH34	22P1A FAB L10	F10A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-F10B-PAH1-AH35	22P1A FAB L10	F10B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10B-PAH1-AH36	22P1A FAB L10	F10B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
E	22P1-F10B-PAH1-AH37	22P1A FAB L10	F10B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-F10B-PAH1-AH38	22P1A FAB L10	F10B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10C-PAH1-AH39	22P1A FAB L10	F10C	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10C-PAH1-AH40	22P1A FAB L10	F10C	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
F	22P1-F10C-PAH1-AH41	22P1A FAB L10	F10C	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-F10C-PAH1-AH42	22P1A FAB L10	F10C	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10D-PAH1-AH43	22P1A FAB L10	F10D	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-F10D-PAH1-AH44	22P1A FAB L10	F10D	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
G	22P1-F10D-PAH1-AH45	22P1A FAB L10	F10D	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10D-PAH1-AH46	22P1A FAB L10	F10D	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10D-PAH1-AH49	22P1A FAB L10	F10D1	1	FORWARD CURVED	6000	250	-	56	37	29.0	20.7	5.0	13.3	1.62	3	3/460/60	-	35	-	MOTOR:IE4
	22P1-F10D-PAH1-AH50	22P1A FAB L10	F10D1	1	FORWARD CURVED	6000	250	-	56	37	29.0	20.7	5.0	13.3	1.62	3	3/460/60	-	35	-	MOTOR:IE4
H	22P1-FB1D-PAH1-AH55	22P1A FAB LB1	UPS-EUV-1	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1D-PAH1-AH56	22P1A FAB LB1	UPS-EUV-1	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1D-PAH1-AH57	22P1A FAB LB1	UPS-EUV-1	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-FB1D-PAH1-AH58	22P1A FAB LB1	UPS-EUV-1	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
I	22P1-F20A-PAH1-AH59	22P1A FAB L20	F20A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-F20A-PAH1-AH60	22P1A FAB L20	F20A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
	22P1-F20A-PAH1-AH61	22P1A FAB L20	F20A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-F20A-PAH1-AH62	22P1A FAB L20	F20A	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60	-	35	-	MOTOR:IE4
J	22P1-F20B-PAH1-AH63	22P1A FAB L20	F20B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
	22P1-F20B-PAH1-AH64	22P1A FAB L20	F20B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
	22P1-F20B-PAH1-AH65	22P1A FAB L20	F20B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4;(FUTURE)
	22P1-F20B-PAH1-AH66	22P1A FAB L20	F20B	1	FORWARD CURVED	20100	250	-	199	129	29.0	20.7	5.0	13.3	5.85	10	3/460/60	-	35	-	MOTOR:IE4
K	22P1-F20C-PAH1-AH67	22P1A FAB L20	F20C	1	FORWARD CURVED	24000	250	-	237	154	29.0	20.7	5.0	13.3	6.9	15	3/460/60				

</

	1	2	3	4	5	6	7	8	9	10	11	12	13	14									
A	PACKAGED SUPPLY FAN SCHEDULE																						
	UNIT MARK	LOCATION	SERVICE	QTY	FAN						MOTOR		FILTER EFF. %		CHEMICAL FILTER			REMARKS					
					TYPE	CMH	TSP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	KW	POWER SOURCE	TYPE	PRE.	FINAL	STAGE 1		STAGE 2	STAGE 3			
	22P1-FB2H-SF2-PK01	22P1B FAB LB2	PCW/UPW/WWT GEX RECOVERY	1	DOUBLE SUCTION	10000	500	FORWARD INCLINED	-	BELT	-	7.5	3/460/60	TEFC	-	-	SPACE		-	-			
	22P1-FB2A-SF1-PK01	22P1A FAB LB2	PCW/UPW/WWT GEX RECOVERY	1	DOUBLE SUCTION	10000	500	FORWARD INCLINED	-	BELT	-	7.5	3/460/60	TEFC	-	-	SPACE	-	-	MOTOR: IE4; 含後制及上側進風風門開關 (濾網適用 MERV 13 室內型, 含預留一進V-type化學濾網空箱段外框 (比開15P6作法) (WITHOUT COOLING COIL) 維修電壓: 1ø/120V/60HZ			
B	AIR HANDLING UNIT SCHEDULE																						
	UNIT MARK	LOCATION	SERVICE	QTY	FAN				COOLING COIL							MOTOR		FILTER EFF. %		REMARKS			
					TYPE	CMH	ESP(pa)	RPM	FACE VEL. M/S MAX.	CAP.(KW)	EAT °C		LAT °C		EWT °C	LWT °C	L/S	HP	POWER SOURCE		TYPE	PRE.	FINAL
											DB	WB	DB	WB									
v	22P1-FB2H-AHU2-AH01	22P1B FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	750	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2H-AHU2-AH02	22P1B FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	750	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2K-AHU2-AH03	22P1B FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	750	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2K-AHU2-AH04	22P1B FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	750	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10H-AHU2-AH05	22P1B FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10H-AHU2-AH06	22P1B FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10H-AHU2-AH07	22P1B FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10H-AHU2-AH08	22P1B FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10K-AHU2-AH09	22P1B FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10K-AHU2-AH10	22P1B FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2A-AHU1-AH01	22P1A FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	700	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2A-AHU1-AH02	22P1A FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	700	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2C-AHU1-AH03	22P1A FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	700	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB2C-AHU1-AH04	22P1A FAB LB2	PCW & UPW	1	BACKWARD CURVED	45400	700	-	2.6	846	35.0	29.4	14.5	14.5	5.0	13.5	23.9	40	3/460/60	TEFC	35	85	MOTOR: IE4; (預留一進V-type化學濾網空箱段外框) (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10A-AHU1-AH05	22P1A FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10A-AHU1-AH06	22P1A FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10A-AHU1-AH07	22P1A FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10A-AHU1-AH08	22P1A FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-F10C-AHU1-AH09	22P1A FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13) (FUTURE)
v	22P1-F10C-AHU1-AH10	22P1A FAB L10	UTILITY SUBFAB	1	BACKWARD CURVED	60000	500	-	2.6	1118	35.0	29.4	14.5	14.5	5.0	13.5	31.6	40	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB1D-AHU1-AH11	22P1A FAB LB1	WWT-A	1	BACKWARD CURVED	30000	500	-	2.6	267	26	20.3	11	11	5.0	13.5	7.5	20	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB1D-AHU1-AH12	22P1A FAB LB1	WWT-A	1	BACKWARD CURVED	30000	500	-	2.6	267	26	20.3	11	11	5.0	13.5	7.5	20	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB1J-AHU2-AH13	22P1B FAB LB1	WWT-B	1	BACKWARD CURVED	15000	500	-	2.6	133	26	20.3	11	11	5.0	13.5	3.8	15	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
v	22P1-FB1J-AHU2-AH14	22P1B FAB LB1	WWT-B	1	BACKWARD CURVED	15000	500	-	2.6	133	26	20.3	11	11	5.0	13.5	3.8	15	3/460/60	TEFC	35	85	MOTOR: IE4; (附進風, 出風, 外氣風門開關) (濾網適用 MERV 13)
F	EXHAUST FAN SCHEDULE																						
	UNIT MARK	LOCATION	SERVICE	QTY	FAN						MOTOR		REMARKS										
					TYPE	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	KW		POWER SOURCE	TYPE								
v	22P1-FB2H-EF2-F01	22P1B FAB LB2	UPW	1	SINGLE INLET CENTRIFUGAL FAN	10000	500	BACKWARD INCLINED	-	BELT	-	7.5	3/460/60	-	MOTOR: IE4; 落地型 (風車轆牛及葉輪材質SUS+內部COATING FRP+軸承外蓋)								
v	22P1-FB2H-EF2-F02	22P1B FAB LB2	UPW	1	SINGLE INLET CENTRIFUGAL FAN	10000	500	BACKWARD INCLINED	-	BELT	-	7.5	3/460/60	-	MOTOR: IE4; 落地型 (STANDBY) (風車轆牛及葉輪材質SUS+內部COATING FRP+軸承外蓋)								
v	22P1-F40G-EF2-F04	22P1B FAB L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-									
v	22P1-F40G-EF2-F05	22P1B FAB L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-									
v	22P1-F40J-EF2-F06	22P1B FAB L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-									
G																							
v	22P1-FB2A-EF1-F01	22P1A FAB LB2	UPW	1	SINGLE INLET CENTRIFUGAL FAN	10000	500	BACKWARD INCLINED	-	BELT	-	7.5	3/460/60	-	MOTOR: IE4; 落地型 (風車轆牛及葉輪材質SUS+內部COATING FRP+軸承外蓋)								
v	22P1-FB2A-EF1-F02	22P1A FAB LB2	UPW	1	SINGLE INLET CENTRIFUGAL FAN	10000	500	BACKWARD INCLINED	-	BELT	-	7.5	3/460/60	-	MOTOR: IE4; 落地型 (STANDBY) (風車轆牛及葉輪材質SUS+內部COATING FRP+軸承外蓋)								
v	22P1-F10C-EF1-F03	22P1B FAB L10	消防機房	1	WALL MOUNTED	8000	62.5	PROPELLER	-	DIRECT	-	0.75	3/460/60	-									
v	22P1-F40B-EF1-F04	22P1A FAB L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-									
v	22P1-F40B-EF1-F05	22P1A FAB L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-									
v	22P1-F40D-EF1-F06	22P1A FAB L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	-	DIRECT	-	0.2	1/208/60	-									
H																							
I																							
J					</																		

1	2	3	4	5	6	7	8	9	10	11	12	13	14
CO2 EXHAUST FAN SCHEDULE													
UNIT MARK	LOCATION	SERVICE	CMH	FAN			WHEEL TYPE	DRIVE	BHP	MOTOR			REMARKS
				TYPE	LSP Pa	FPM				POWER KW	VOLTAGE	TYPE	
22P1-FR1H-CEX2-F01	22P1B FAB LR1	ELECTRICAL ROOM	20000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1K-CEX2-F02	22P1B FAB LR1	ELECTRICAL ROOM	20000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1K-CEX2-F03	22P1B FAB LR1	ELECTRICAL ROOM	4000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	1.5	3/460/60	TEFC	屋外強制型
22P1-FR1G-CEX2-F04	22P1B FAB LR1	ELECTRICAL ROOM	20000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1J-CEX2-F05	22P1B FAB LR1	ELECTRICAL ROOM	17000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1J-CEX2-F06	22P1B FAB LR1	ELECTRICAL ROOM	12000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1A-CEX1-F01	22P1B FAB LR1	ELECTRICAL ROOM	20000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1C-CEX1-F02	22P1B FAB LR1	ELECTRICAL ROOM	20000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1C-CEX1-F03	22P1B FAB LR1	ELECTRICAL ROOM	4000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	1.5	3/460/60	TEFC	屋外強制型
22P1-FR1B-CEX1-F04	22P1A FAB LR1	ELECTRICAL ROOM	20000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1D-CEX1-F05	22P1A FAB LR1	ELECTRICAL ROOM	17000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型
22P1-FR1D-CEX1-F06	22P1A FAB LR1	ELECTRICAL ROOM	12000	INLINE FAN	500	-	BACKWARD INCLINED	BELT	-	5.5	3/460/60	TEFC	屋外強制型

UPW/DI BUFFER TANK SCHEDULE						
UNIT MARK	SERVICE	QTY	MATERIAL	EFFECTIVE TANK CAPACITY (M ³)	DIMENSION (mm)	REMARKS
22P1-FB2H-DIW2-T01	22P1B UPW/DI MAKE UP TANK	1	SUS 316	15		
22P1-FB2A-DIW1-T01	22P1A UPW/DI MAKE UP TANK	1	SUS 316	15		



UPW/DI PUMP SCHEDULE													
UNIT MARK	SERVICE	TYPE	SUCTION SIZE A	DISCHARGE SIZE A	FLOW L/S	HEAD M	BHP	RPM	MOTOR			FLUID	REMARKS
									POWER (KW)	VOLTAGE	TYPE		
22P1-FB2H-DIW2-P01	22P1B UPW/DI MAKE UP WATER SYSTEM	IN-LINE	100	100	17.5	68	-	3500	19	3/460/60	ODP	DI WATER	W/VFD,IE3 SUS 横
22P1-FB2H-DIW2-P02	22P1B UPW/DI MAKE UP WATER SYSTEM	IN-LINE	100	100	17.5	68	-	3500	19	3/460/60	ODP	DI WATER	W/VFD,IE3 SUS 横
22P1-FB2H-DIW2-P03	22P1B UPW/DI MAKE UP WATER SYSTEM	IN-LINE	100	100	17.5	68	-	3500	19	3/460/60	ODP	DI WATER	W/VFD,IE3 SUS 横(STANDBY)
22P1-FB2A-DIW1-P01	22P1A UPW/DI MAKE UP WATER SYSTEM	IN-LINE	100	100	17.5	68	-	3500	19	3/460/60	ODP	DI WATER	W/VFD,IE3 SUS 横
22P1-FB2A-DIW1-P02	22P1A UPW/DI MAKE UP WATER SYSTEM	IN-LINE	100	100	17.5	68	-	3500	19	3/460/60	ODP	DI WATER	W/VFD,IE3 SUS 横
22P1-FB2A-DIW1-P03	22P1A UPW/DI MAKE UP WATER SYSTEM	IN-LINE	100	100	17.5	68	-	3500	19	3/460/60	ODP	DI WATER	W/VFD,IE3 SUS 横(STANDBY)

PLATE TYPE HEAT EXCHANGER SCHEDULE													
UNIT MARK	SERVICE	CAPACITY KW	COLD SIDE					HOT SIDE				REMARKS	
			EWT °C	LWT °C	L/S	WTR ΔP KPa	FLUID	EWT °C	LWT °C	L/S	WTR ΔP KPa		FLUID
22P1-F40A-7CH1-HX01	7°C CHILLED WATER SYSTEM	5550	5	13	166.5	<50	WATER	15	7	166.5	<50	WATER	
22P1-F40A-7CH1-HX02	7°C CHILLED WATER SYSTEM	5550	5	13	166.5	<50	WATER	15	7	166.5	<50	WATER	
22P1-F40A-7CH1-HX03	7°C CHILLED WATER SYSTEM	5550	5	13	166.5	<50	WATER	15	7	166.5	<50	WATER	(FUTURE)
22P1-F40A-33WW1-HX01	33°C WARM WATER SYSTEM	1760	27	33	70.4	<50	WATER	35	29	70.4	<50	WATER	
22P1-F40A-33WW1-HX02	33°C WARM WATER SYSTEM	1760	27	33	70.4	<50	WATER	35	29	70.4	<50	WATER	(FUTURE)

HVAC PUMP SCHEDULE													
UNIT MARK	SERVICE	TYPE	SUCTION SIZE A	DISCHARGE SIZE A	FLOW L/S	HEAD M	BHP	RPM	MOTOR		FLUID	REMARKS	
									KW	VOLTAGE			TYPE
22P1-F40A-7CH1-P01	7°C CHILLED WATER SYSTEM	IN-LINE	250	250	165	30	-	-	75	3/460/60	TEFC	WATER	W/VFD ,IE3
22P1-F40A-7CH1-P02	7°C CHILLED WATER SYSTEM	IN-LINE	250	250	165	30	-	-	75	3/460/60	TEFC	WATER	W/VFD ,IE3
22P1-F40A-7CH1-P03	7°C CHILLED WATER SYSTEM	IN-LINE	250	250	165	30	-	-	75	3/460/60	TEFC	WATER	W/VFD ,IE3 (STANDBY)
22P1-F40A-7CH1-P04	7°C CHILLED WATER SYSTEM	IN-LINE	250	250	165	30	-	-	75	3/460/60	TEFC	WATER	W/VFD ,IE3 (FUTURE)
22P1-F40A-33WW1-P01	33°C WARM WATER SYSTEM	IN-LINE	150	150	70	30	-	-	30	3/460/60	TEFC	WATER	W/VFD ,IE3
22P1-F40A-33WW1-P02	33°C WARM WATER SYSTEM	IN-LINE	150	150	70	30	-	-	30	3/460/60	TEFC	WATER	W/VFD ,IE3 (STANDBY)
22P1-F40A-33WW1-P03	33°C WARM WATER SYSTEM	IN-LINE	150	150	30	30	-	-	30	3/460/60	TEFC	WATER	W/VFD ,IE3 (FUTURE)

JET INDUCE FAN SCHEDULE														
UNIT MARK	LOCATION	SERVICE	QTY	FAN							MOTOR			REMARKS
				TYPE	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	HP	POWER SOURCE	TYPE	
IF	22P1 FAB LB1	LB1中央走廊	5	誘導式-INLINED	2500	150	FORWARD CURVED	-	-	-	0.5 HP	1/208/60	-	

AIR CURTAIN SCHEDULE											
UNIT MARK	LOCATION	SERVICE	QTY	FAN		SIZE		MOTOR			REMARKS
				有效遮斷距離 (m)	CMM	W (mm)	H (mm)	W	POWER SOURCE	TYPE	
22P1-F10A-SF1-F01	22P1A FAB L10	FAB 出入口	1	3.5	43	1200	200	194	3/220/60	—	
22P1-F10A-SF1-F02	22P1A FAB L10	FAB 出入口	1	3.5	43	1200	200	194	3/220/60	—	
22P1-F10H-SF1-F01	22P1A FAB L10	FAB 出入口	1	3.5	43	1200	200	194	3/220/60	—	
22P1-F10H-SF1-F02	22P1A FAB L10	FAB 出入口	1	3.5	43	1200	200	194	3/220/60	—	

[illegible]

台灣積體電路製造股份有限公司
Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE
---------------------	------	---------------------	------

CONTRACTOR



漢唐集成股份有限公司

DRAWN ROGER YE	DATE 2024/02/27	RECHECKED Steven Yu	DATE 2024/02/27
DESIGNED ROGER YE	DATE 2024/02/27	APPROVED JOSEPH LEE	DATE 2024/02/27

TITL

MECHANICAL SYSTEM
EQUIPMENT SCHEDULE
(11)
HPM

PROJECT	FAB22 Phase 1 PROJECT
---------	-----------------------

PACKAGE NAME	MEP SYSTEM
--------------	------------

DRAWING NAME	F22P1-M-1-F-04
--------------	----------------

SCAN

NOT TO SCALE

FILE NAME F22P1-M-1-F-04

Rev.

	1	2	3	4	5	6	7	8	9	10	11	12	13	14																		
A	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	UNIT MARK	LOCATION	SERVICE	FAN						HEATING COIL																						
				CMH	ESP(pa)	TSP(pa)	WHEEL TYPE	DRIVE	RPM	EFFICIENCY %	FACE VEL M/S MAX	ROWS/FP	CAP.KW	EAT DB°C	LAT DB°C	AIR Δ P Pa	L/S	EWT °C	LWT °C	WTR Δ P KPa	FACE VEL M/S MAX	ROWS/FP	CAP.KW	EAT DB°C	LAT DB°C	AIR Δ P Pa	L/S	EWT °C	LWT °C	WTR Δ P KPa		
	22P1-H40L-MAU2-AH41	22P1B HPM L40	GAS/CHEM. ROOM	145000	700	2400	BACKWARD INCLINED	DIRECT	-	-	-	-	-	-	-	-	-	-	-	-	2.66	-	2067	35	29.4	19.0	18.9	-	58	12	20.6	-
	22P1-H40L-MAU2-AH42	22P1B HPM L40	GAS/CHEM. ROOM	145000	700	2400	BACKWARD INCLINED	DIRECT	-	-	-	-	-	-	-	-	-	-	-	-	2.66	-	2067	35	29.4	19.0	18.9	-	58	12	20.6	-
	22P1-H40L-MAU2-AH43	22P1B HPM L40	GAS/CHEM. ROOM	145000	700	2400	BACKWARD INCLINED	DIRECT	-	-	-	-	-	-	-	-	-	-	-	-	2.66	-	2067	35	29.4	19.0	18.9	-	58	12	20.6	-
B	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
C	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
D	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
E	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
F	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
G	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
H	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
I	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
J	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															
	MAKE-UP AIR HANDLING UNIT SCHEDULE																															

KEY PLAN

MECHANICAL SYSTEM EQUIPMENT SCHEDULE (6) HPM

PROJECT

FAB22 Phase 1 PROJECT

PACKAGE NAME

MEP SYSTEM

DRAWING NAME

F22P1-M-1-H-01

SCALE

NOT TO SCALE

UNIT

mm

FILE NAME

F22P1-M-1-H-01

Rev

ACCEPTANCE REVIEWED

DATE

ACCEPTANCE REVIEWED

DATE

CONTRACTOR

漢唐集成股份有限公司

DRAWN

ROGER YEH

DATE

2024/02/27

RECHECKED

Steven Yu

DATE

2024/02/27

DESIGNED

ROGER YEH

DATE

2024/02/27

APPROVED

JOSEPH LEE

DATE

2024/02/27

Serial number: 202501201326-14437217

出圖日期: 2024/02/27

1

2

3

4

5

6

7

8

9

10

11

12

13

14

A

B

C

D

E

F

G

H

I

J

FAN COIL UNIT SCHEDULE																						
UNIT MARK	QTY	AIR FLOW CMH	ESP(pa)	COOLING COIL								HEATING COIL						MOTOR			REMARKS	
				TOTAL KW	SENSIBLE KW	EAT °C		LAT °C		L/S	EWT °C	LWT °C	CAP. KW	EAT °C DB	L/S	EWT °C	LWT °C	WATTS	POWER SOURCE	TYPE		
						DB	WB	DB	WB													
④	—	684	50	4.33	2.63	25	20	—	—	0.21	5	10	—	—	—	—	—	95	1/208/60	—	吊掛隱藏式小型送風機（附溫度控制器及控制面板）	CEILING RECESSED TYPE W/R.A. BOX & FILTER
⑥	—	1044	50	5.76	3.54	25	20	—	—	0.28	5	10	—	—	—	—	—	142	1/208/60	—	吊掛隱藏式小型送風機（附溫度控制器及控制面板）	CEILING RECESSED TYPE W/R.A. BOX & FILTER
⑧	2	1332	50	8.01	4.83	25	20	—	—	0.39	5	10	—	—	—	—	—	166	1/208/60	—	吊掛隱藏式小型送風機（附溫度控制器及控制面板）	CEILING RECESSED TYPE W/R.A. BOX & FILTER
⑩	—	1728	50	9.58	5.87	25	20	—	—	0.46	5	10	—	—	—	—	—	228	1/208/60	—	吊掛隱藏式小型送風機（附溫度控制器及控制面板）	CEILING RECESSED TYPE W/R.A. BOX & FILTER
⑫	—	2052	50	10.92	6.82	25	20	—	—	0.53	5	10	—	—	—	—	—	285	1/208/60	—	吊掛隱藏式小型送風機（附溫度控制器及控制面板）	CEILING RECESSED TYPE W/R.A. BOX & FILTER
△④	2	684	50	4.33	2.63	25	20	—	—	0.21	5	10	—	—	—	—	—	95	1/208/60	—	吊掛露明式小型送風機（附溫度控制器及控制面板）	
△⑥	—	1044	50	5.76	3.54	25	20	—	—	0.28	5	10	—	—	—	—	—	142	1/208/60	—	吊掛露明式小型送風機（附溫度控制器及控制面板）	
△⑧	13	1332	50	8.01	4.83	25	20	—	—	0.39	5	10	—	—	—	—	—	166	1/208/60	—	吊掛露明式小型送風機（附溫度控制器及控制面板）	
△⑩	—	1728	50	9.58	5.87	25	20	—	—	0.46	5	10	—	—	—	—	—	228	1/208/60	—	吊掛露明式小型送風機（附溫度控制器及控制面板）	
△⑫	4	2052	50	10.92	6.82	25	20	—	—	0.53	5	10	—	—	—	—	—	285	1/208/60	—	吊掛露明式小型送風機（附溫度控制器及控制面板）	
⑫	2	2052	50	10.92	6.82	25	—	—	—	0.53	5	10	10.92	18	0.53	35	30	285	1/120/60	—	吊掛露明式小型送風機（附溫度控制器及控制面板）	比例式控制（HPM L10 AW ST-250）


EXHAUST FAN SCHEDULE																
UNIT MARK	LOCATION	SERVICE	QTY	FAN						MOTOR			REMARKS			
				TYPE	CMH	ESP(pa)	WHEEL TYPE	RPM	DRIVE	BHP	KW	POWER SOURCE		TYPE		
22P1-HB2L-EF2-F01	22P1B HPM LB2	WWT	1	SINGLE INLET CENTRIFUGAL FAN	45000	500	BACKWARD INCLINED	—	BELT	—	14.9	3/460/60	—	MOTOR: IE4; 落地型		
22P1-HB2L-EF2-F02	22P1B HPM LB2	WWT	1	SINGLE INLET CENTRIFUGAL FAN	45000	500	BACKWARD INCLINED	—	BELT	—	14.9	3/460/60	—	MOTOR: IE4; 落地型		
22P1-H40L-EF2-F03	22P1B HPM L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	—	DIRECT	—	0.2	1/208/60	—			
22P1-HB2E-EF1-F01	22P1A HPM LB2	WWT	1	SINGLE INLET CENTRIFUGAL FAN	45000	500	BACKWARD INCLINED	—	BELT	—	14.9	3/460/60	—	MOTOR: IE4; 落地型		
22P1-HB2E-EF1-F02	22P1A HPM LB2	WWT	1	SINGLE INLET CENTRIFUGAL FAN	45000	500	BACKWARD INCLINED	—	BELT	—	14.9	3/460/60	—	MOTOR: IE4; 落地型		
22P1-H40E-EF1-F03	22P1A HPM L40	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	—	DIRECT	—	0.2	1/208/60	—			
22P1-HR1E-EF1-F04	22P1A HPM LR1	廁所/茶水間	1	INLINE FAN	25000	500	BACKWARD INCLINED	—	BELT	—	7.5	3/460/60	—	MOTOR: IE4; 屋外落地型		
22P1-HR1E-EF1-F06	22P1A HPM LR1	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	—	DIRECT	—	0.2	1/208/60	—			
22P1-HR1E-EF1-F07	22P1A HPM LR1	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	—	DIRECT	—	0.2	1/208/60	—			
22P1-HR2E-EF1-F08	22P1A HPM LR2	電梯機房	1	WALL MOUNTED	2300	62.5	PROPELLER	—	DIRECT	—	0.2	1/208/60	—			
22P1-HB1E-EF1-F09	22P1B HPM LB2	廁所/茶水間	1	INLINE FAN	8100	250	FORWARD CURVED	—	BELT	—	2.2	3/460/60	—	MOTOR: IE4; 室內吊掛型		


EXHAUST FAN SCHEDULE（透浦型風機）																
UNIT MARK	LOCATION	SERVICE	QTY	FAN						MOTOR			REMARKS			
				TYPE	CMH	ESP(mmAq)	WHEEL TYPE	RPM	DRIVE	BHP	KW	POWER SOURCE		TYPE		
22P1-HR2E-EF1-F09	22P1A HPM LR2	LB2（化糞池）	1	透浦型風機	700	485(48.5)	—	—	DIRECT	—	3.75(2P)	3/460/60	—	MOTOR: IE4; 屋外落地型		
22P1-HR2E-EF1-F10	22P1A HPM LR2	LB2（化糞池）	1	透浦型風機	700	485(48.5)	—	—	DIRECT	—	3.75(2P)	3/460/60	—	MOTOR: IE4; 屋外落地型（STANDBY）		

CO2 EXHAUST FAN SCHEDULE															
UNIT MARK	LOCATION	SERVICE	CMH	FAN				MOTOR							REMARKS
				TYPE	ESP Pa	FRPM	WHEEL TYPE	DRIVE	BHP	POWER (KW)	VOLTAGE	TYPE			
22P1-H40L-CEX2-F01	22P1B HPM L40	ELECTRICAL ROOM	31000	INLINE FAN	500	—	BACKWARD INCLINED	BELT	—	11	3/460/60	ODP	—	室內吊掛型	
22P1-H40E-CEX1-F01	22P1A HPM L40	ELECTRICAL ROOM	31000	INLINE FAN	500	—	BACKWARD INCLINED	BELT	—	11	3/460/60	ODP	—	室內吊掛型	
22P1-HR1E-CEX1-F02	22P1A HPM LR1	VOC PANEL ROOM	6000	INLINE FAN	250	—	FORWARD CURVED	BELT	—	1.5	3/460/60	ODP	—	室內吊掛型	


20240111配合變電站面積調整


AIR CURTAIN SCHEDULE											
UNIT MARK	LOCATION	SERVICE	QTY	FAN		SIZE		MOTOR			REMARKS
				有效遮斷距離 (m)	CMM	W (mm)	H (mm)	W	POWER SOURCE	TYPE	
22P1-H10E-SF1-F01,02	22P1A HPM L10	HPM 隔噪區	2	3.5	43	1200	200	194	3/220/60	—	
22P1-H10E-SF1-F03,04,05,06	22P1A HPM L10	HPM 隔噪區	4	3.5	43	1200	200	194	3/220/60	—	
22P1-H10L-SF2-F01,02	22P1A HPM L10	HPM 隔噪區	2	3.5	43	1200	200	194	3/220/60	—	
22P1-H10L-SF2-F03,04,05,06	22P1A HPM L10	HPM 隔噪區	4	3.5	43	1200	200	194	3/220/60	—	




版本 VER.	日期 DATE	修正者 REV BY	修 正 REVISION
 台灣積體電路製造股份有限公司 Taiwan Semiconductor Manufacturing Company, Ltd.			
ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE
CONTRACTOR			
 漢唐集成股份有限公司			
DRAWN ROGER YEH	DATE 2024/02/27	CHECKED Steven Yu	DATE 2024/02/27
DESIGNED ROGER YEH	DATE 2024/02/27	APPROVED JOSEPH LEE	DATE 2024/02/27
TITLE			
MECHANICAL SYSTEM EQUIPMENT SCHEDULE (7) HPM			
PROJECT FAB22 Phase 1 PROJECT			
PACKAGE NAME MEP SYSTEM			
DRAWING NAME F22P1-M-1-H-02			
SCALE			UNIT
NOT TO SCALE			mm
FILE NAME F22P1-M-1-H-02			Rev.

	1	2	3	4	5	6	7	8	9	10	11	12	13	14				
A	HEATING COIL SCHEDULE																	
	UNIT MARK	LOCATION	SERVICE	QTY	CMH	FACE VEL M/S MAX	ROWS/FP	CAP.KW	EAT DB°C	LAT DB°C	AIR Δ P Pa	L/S	PIPING A	EWT °C	LWT °C	WTR Δ P KPa	DUCT SIZE W X H (mm)	REMARKS
	22P1-H10E-HC1-C01	22P1A HPM L10	Solvent Bottle	1	1200	4	1/2	1.6	18	22	<45	0.1	20	35	29	-	-	
	22P1-H10E-HC1-C02	22P1A HPM L10	Mixing Chemical Caustic	1	6600	4	1/2	8.9	18	22	<45	0.35	20	35	29	-	-	
B	22P1-H10E-HC1-C03	22P1A HPM L10	Solvent DHL	1	7900	4	1/2	10.6	18	22	<45	0.42	25	35	29	-	-	
	22P1-H10E-HC1-C04	22P1A HPM L10	Solvent DHL	1	14500	4	1/2	19.5	18	22	<45	0.8	32	35	29	-	-	
	22P1-H10E-HC1-C05	22P1A HPM L10	DCS	1	28000	4	1/2	37.7	18	22	<45	1.5	40	35	29	-	-	
	22P1-H10E-HC1-C06	22P1A HPM L10	HF25 Lorry	1	3200	4	1/2	4.3	18	22	<45	0.17	20	35	29	-	-	
	22P1-H10E-HC1-C07	22P1A HPM L10	Solvent(異種)-3	1	1200	4	1/2	1.6	18	22	<45	0.1	40	35	29	-	-	
	22P1-H10E-HC1-C08	22P1A HPM L10	Solvent(異種)-2	1	1200	4	1/2	1.6	18	22	<45	0.1	20	35	29	-	-	
	22P1-H10E-HC1-C09	22P1A HPM L10	Caustic DHL	1	20000	4	1/2	26.9	18	22	<45	1.07	32	35	29	-	-	
	22P1-H10E-HC1-C10	22P1A HPM L10	Acid DHL / Fluoride DHL	1	29000	4	1/2	39.1	18	22	<45	1.56	40	35	29	-	-	
	22P1-H10E-HC1-C11	22P1A HPM L10	Solvent(異種)-1	1	1500	4	1/2	2	18	22	<45	0.1	20	35	29	-	-	
	22P1-H10E-HC1-C12	22P1A HPM L10	H2O2/H2O2/NH4OH/DEVELOPER-1	1	12200	4	1/2	16.4	18	22	<45	0.65	25	35	29	-	-	
C	22P1-H10E-HC1-C13	22P1A HPM L10	H2O2/HCL/FNDP001/Thinner-3/IPA/Thinner-1/HF49	1	22000	4	1/2	29.6	18	22	<45	1.18	32	35	29	-	-	
	22P1-H10L-HC2-C01	22P1B HPM L10	MIXING CHEMICAL CAUSTIC	1	10000	4	1/2	13.5	18	22	<45	0.54	25	35	29	-	-	
	22P1-H10L-HC2-C02	22P1B HPM L10	Solvent DHL	1	7900	4	1/2	10.6	18	22	<45	0.42	25	35	29	-	-	
	22P1-H10L-HC2-C03	22P1B HPM L10	Solvent DHL	1	14500	4	1/2	19.5	18	22	<45	0.78	32	35	29	-	-	
	22P1-H10L-HC2-C04	22P1B HPM L10	DCS	1	29000	4	1/2	39.1	18	22	<45	1.56	40	35	29	-	-	
D	22P1-H10L-HC2-C05	22P1B HPM L10	SPARE(Caustic)	1	3200	4	1/2	4.3	18	22	<45	0.17	20	35	29	-	-	
	22P1-H10L-HC2-C06	22P1B HPM L10	Solvent(異種)-4	1	1500	4	1/2	2	18	22	<45	0.1	20	35	29	-	-	
	22P1-H10L-HC2-C07	22P1B HPM L10	Caustic DHL	1	14000	4	1/2	18.9	18	22	<45	0.75	25	35	29	-	-	
	22P1-H10L-HC2-C08	22P1B HPM L10	Acid DHL / Fluoride DHL	1	20000	4	1/2	26.9	18	22	<45	1.07	32	35	29	-	-	
	22P1-H10L-HC2-C09	22P1B HPM L10	Solvent(異種)-5	1	1500	4	1/2	2	18	22	<45	0.1	20	35	29	-	-	
	22P1-H10L-HC2-C10	22P1B HPM L10	DEVELOPER-1/NH4OH	1	6400	4	1/2	8.6	18	22	<45	0.34	20	35	29	-	-	
	22P1-H10L-HC2-C11	22P1B HPM L10	SPARE/H2SO4/SPARE/Thinner-1/IPA/FN-DP001/H2O2	1	21100	4	1/2	28.4	18	22	<45	1.13	32	35	29	-	-	
	22P1-H20E-HC1-C01	22P1A HPM L20	Slurry Room	1	48000	4	1/2	64.7	18	22	<45	2.58	50	35	29	-	-	
	22P1-H20E-HC1-C02	22P1A HPM L20	H2O2	1	4000	4	1/2	5.4	18	22	<45	0.22	20	35	29	-	-	
	22P1-H20E-HC1-C03	22P1A HPM L20	CAUSTIC	1	30000	4	1/2	40.4	18	22	<45	1.61	40	35	29	-	-	
E	22P1-H20E-HC1-C04	22P1A HPM L20	ACID	1	29000	4	1/2	39.1	18	22	<45	1.56	40	35	29	-	-	
	22P1-H20E-HC1-C05	22P1A HPM L20	Solvent	1	22500	4	1/2	30.3	18	22	<45	1.21	32	35	29	-	-	
	22P1-H20E-HC1-C06	22P1A HPM L20	HF	1	12000	4	1/2	16.2	18	22	<45	0.65	25	35	29	-	-	
	22P1-H20E-HC1-C07	22P1A HPM L20	Corrosive & Inert Gas	1	54000	4	1/2	72.7	18	22	<45	2.89	50	35	29	-	-	
	22P1-H20E-HC1-C08	22P1A HPM L20	Extremely Explode Gas	1	4000	4	1/2	5.4	18	22	<45	0.22	20	35	29	-	-	
F	22P1-H20E-HC1-C09	22P1A HPM L20	Extremely Toxic Gas	1	4200	4	1/2	5.7	18	22	<45	0.23	20	35	29	-	-	
	22P1-H20E-HC1-C10	22P1A HPM L20	Flammable Gas	1	32000	4	1/2	43.1	18	22	<45	1.72	40	35	29	-	-	
	22P1-H20E-HC1-C11	22P1A HPM L20	CLF3 Gas	1	5000	4	1/2	6.7	18	22	<45	0.27	20	35	29	-	-	
	22P1-H20L-HC2-C01	22P1B HPM L20	HF	1	11000	4	1/2	14.8	18	22	<45	0.59	25	35	29	-	-	
	22P1-H20L-HC2-C02	22P1B HPM L20	Slurry / Caustic	1	59500	4	1/2	80.1	18	22	<45	3.19	50	35	29	-	-	
	22P1-H20L-HC2-C03	22P1B HPM L20	ACID	1	23500	4	1/2	31.7	18	22	<45	1.26	32	35	29	-	-	
	22P1-H20L-HC2-C04	22P1B HPM L20	Solvent Room	1	19000	4	1/2	25.6	18	22	<45	1.02	32	35	29	-	-	
G	22P1-H20L-HC2-C05	22P1B HPM L20	H2O2 Room	1	6500	4	1/2	8.8	18	22	<45	0.35	20	35	29	-	-	
	22P1-H20L-HC2-C06	22P1B HPM L20	Corrosive & Inert Gas	1	49500	4	1/2	66.7	18	22	<45	2.66	50	35	29	-	-	
	22P1-H20L-HC2-C07	22P1B HPM L20	Extremely Explode Gas	1	4000	4	1/2	5.4	18	22	<45	0.22	20	35	29	-	-	
	22P1-H20L-HC2-C08	22P1B HPM L20	Extremely Toxic Gas	1	4200	4	1/2	5.7	18	22	<45	0.23	20	35	29	-	-	
	22P1-H20L-HC2-C09	22P1B HPM L20	Flammable Gas	1	31000	4	1/2	41.8	18	22	<45	1.66	40	35	29	-	-	
	22P1-H20L-HC2-C10	22P1B HPM L20	CLF3 Gas	1	5000	4	1/2	6.7	18	22	<45	0.27	20	35	29	-	-	
	H																	
I																		
J																		
	1	2	3	4	5	6	7	8	9	10	11	12	13	14				



版本 VER.	日期 DATE	修正者 REV BY		修 正 REVISION	
					
台灣積體電路製造股份有限公司 Taiwan Semiconductor Manufacturing Company, Ltd.					
ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE		
CONTRACTOR					
 漢唐集成股份有限公司					
DRAWN	ROGER YEH	DATE	2024 / 02 / 27	CHECKED	Steven Yu
DESIGNED	ROGER YEH	DATE	2024 / 02 / 27	APPROVED	JOSEPH LEE
				UNIT	m m
TITLE					
MECHANICAL SYSTEM EQUIPMENT SCHEDULE (1) HPM					
PROJECT FAB22 Phase 1 PROJECT					
PACKAGE NAME MEP SYSTEM					
DRAWING NAME F22P1-M-1-H-03					
SCALE NOT TO SCALE					Rev.
FILE NAME F22P1-M-1-H-03					



KEY PLANT

Building Code

- A: Office
- F: FAB
- H: HPM
- C: CUP
- G: Gas Yard & BSGS
- S: Supporting
- N: ASC
- W: Warehouse

VER.	DATE	修正者	修正

台灣積體電路製造股份有限公司
Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE

CONTRACTOR

漢唐集成股份有限公司
United Integrated Services


DRAWN	TCM	DATE	RECHECKED	Steven Yu	DATE
DESIGNED	TCM	DATE	APPROVED	JOSEPH LEE	DATE

TITLE

**FLOW DIAGRAM
COOLING TOWER
FILTRATIONS SYSTEM**

PROJECT	FAB22 Phase 1 PROJECT
PACKAGE NAME	MEP SYSTEM
DRAWING NAME	F22P1-M-2-C-06
SCALE	NOT TO SCALE
FILE NAME	F22P1-M-2-C-06

UNIT	mm
Rev	



- NOTE :
1. 本系統不論何種藥劑的配管全部使用VC SCH80.
 2. 在防液堤外管路用雙套管.
 3. 防液堤內除了加藥灌裝口至冷卻水漂白及防蝕防垢劑桶槽之間配管用雙套管外,其他都不是雙套管.
 4. 防液堤不屬本工程
 5. 防液堤內設備基礎mm 廠P COATING 屬EP SCOPE .
 6. 防液堤內OOPING (洩水坡度)屬EP SCOPE .
 7. 信號回傳符號說明:
(加藥室至中控室的信號線屬冰機廠商)
- HH 化學藥桶高位警報.
 - H 化學藥桶高位警報.
 - L 化學藥桶低位警報.
 - LL 化學藥桶低位警報.
 - ACID DLK 酸性DIKE漏液檢知警報.
 - ALKA DLK 鹼性DIKE漏液檢知警報.
 - LK 雙層管內漏液警報.

KEY PLANT

Building Code

- A: Office
- F: FAB
- C: CUP
- G: Gas Yard & BSGS
- N: Supporting
- W: Warehouse

台積電

台灣積體電路製造股份有限公司

Taiwan Semiconductor Manufacturing Company, Ltd.

紙次	日期	修正者	修正
VER.	DATE	REVIEW	REVISION

CONTRACTOR	DATE	RECHECKED	DATE
漢唐集成股份有限公司	2024/02/27	Steven Yu	2024/02/27

DRAWN	DATE	RECHECKED	DATE
TCM	2024/02/27	JOSEPH LEE	2024/02/27

PROJECT: FAB22 Phase 1 PROJECT

PACKAGE NAME: MEP SYSTEM


DRAWING NAME: F22P1-M-2-C-07



SCALE: NOT TO SCALE

FILE NAME: F22P1-M-2-C-07

Unit: mm

Rev:





ACCEPTANCE REVIEWED				DATE			
CONTRACTOR				DATE			
DRAWN				DATE			
DESIGNED				DATE			
TITLE				DATE			
PROJECT				DATE			
PACKAGE NAME				DATE			
DRAWING NAME				DATE			
SCALE				DATE			
FILE NAME				DATE			



KEY PLAN

Building Code

- A: Office
- F: FAB
- H: HPM
- C: CUP
- G: Gas Yard & BSGS
- S: Supporting
- N: ASC
- W: Warehouse

版本	日期	修正者	修正
VER.	DATE	REVIEW	REVISION

台积电

台灣積體電路製造股份有限公司

Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE


CONTRACTOR

uis 漢唐集成股份有限公司

United Integrated Service

DRAWN	ROGER YEH	DATE	2024/02/27	RECHECKED	Steven Yu	DATE	2024/02/27
DESIGNED	ROGER YEH	DATE	2024/02/27	APPROVED	JOSEPH LEE	DATE	2024/02/27
TITLE							
FLOW DIAGRAM- DUCTING SYSTEM (1) CUP							
PROJECT							
FAB22 Phase 1 PROJECT							
PACKAGE NAME							
MEP SYSTEM							
DRAWING NAME							
F22P1-M-2-C-10							
SCALE							
NOT TO SCALE							
UNIT							
mm							
FILE NAME							
F22P1-M-2-C-10							
Rev							


出圖日期: 2024/02/27





C02 風機規格計算書



排気設備		排気区大面積為 595.7 ㎡,總體積為 6 m ³ ,容積 3575 m ³							
1. 排気設備		595.7 ㎡ x 6 m x 5 次/時 =17875 m ³ /HR							
2. 排気設備		容積排気設備-由 22000 CMH(366.7CMM)							
3. 排気設備		排気管 0.7m x 0.8m							
4. 排気設備		Q/A/60=366.7/60=6.111 M/S							
5. 排気設備		1. 115m x 0.45m 2. 13m x 0.4m 3. 12m x 0.45m 4. 0.6m x 1.0m 5. 0.8m x 0.9m							
6. 排気設備		1. V=11.8 M/S 2. V=11.7 M/S 3. V=11.3 M/S 4. V=10.1 M/S 5. V=8.4 M/S							
部	1. 直徑規格		規格尺寸 (mm)	風量 (CMM)	風速 (M/S)	動壓 (mmHg/m)	容積 (m ³)	重量 (mmHg)	
			1. 115m x 0.45m	366.7	11.8	0.21	8	1.68	
			2. 13m x 0.4m	366.7	11.7	0.22	6	1.32	
			3. 12m x 0.45m	366.7	11.3	0.19	17	3.23	
			4. 1.0m x 0.6m	366.7	10.1	0.13	10	1.3	
			5. 0.8m x 0.9m	366.7	8.4	0.08	15	1.2	
			合計					8.73	
	2. 排気設備質量		P ₂ = F x (Vg / 4.037 x N = 0.5 x 0.118 / 4.037 x 5)						4.28
	3. 排気管質量		P ₂ = F x (Vg / 4.037 x N = 0.15 x 0.118 / 4.037 x 5)						6.4
	4. 重量合計								-
部	5. 50%容積		207/(1+0.2+0.4+0.207)						3.88
	6. 60%容積		500Pa (50mmHg)						23.29
			動壓計算式:風速=11.8 M/S P ₂ = Vg ² / 4.037 = (11.8 / 4.037) ²						8.5
	7. 全壓力								31.79
風機所需電力		KW=(0.3xP ₂ /(6120x0.6x1) =366.7x1.79/(6120x0.6x1) =3.5 kw 選擇用 7.5KW>3.5 KW,DK							

排機： 2P2P-CRIP-C03X3-F01	
尺寸： 長x寬x高	22000 CMH(366.7CMM) x 1
排機： 500 Pa(50mmHg)	
馬力： 7.5 W, 304P 460V	







次 VER.	日期 DATE	修正者 REV BY	修正 REVISION
			
台灣積體電路製造股份有限公司 Taiwan Semiconductor Manufacturing Company, Ltd.			
ACCEPTANCE REVIEWED		DATE	ACCEPTANCE REVIEWED
		DATE	
CONTRACTOR			
 漢唐集成股份有限公司			
DRAWN	ROGER YEH	DATE 2024/02/21	RECHECKED Stereon Yu
DESIGNED	ROGER YEH	DATE 2024/02/27	APPROVED JOSEPH LEE
TITLE			
FLOW DIAGRAM- PIPING SYSTEM (1) FAB A			
PROJECT FAB22 Phase 1 PROJECT			
PACKAGE NAME MEP SYSTEM			
DRAWING NAME F22P1-M-2-F-01			
SCALE			UNIT mm
NOT TO SCALE			
FILE NAME F22P1-M-2-F-01			Rev.





版本	日期	修正者	修正
VER.	DATE	REVIEW	REVISION
台灣積體電路製造股份有限公司 Taiwan Semiconductor Manufacturing Company, Ltd.			
ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE
CONTRACTOR 漢唐集成股份有限公司 United Integrated Services			
DRAWN	ROGER YEH	DATE	2024/02/27
DESIGNED	ROGER YEH	DATE	2024/02/27
TITLE FLOW DIAGRAM- PIPING SYSTEM (2) FAB B			
PROJECT FAB22 Phase 1 PROJECT			
PACKAGE NAME MEP SYSTEM			
DRAWING NAME F22P1-M-2-F-02			
SCALE	NOT TO SCALE		UNIT mm
FILE NAME	F22P1-M-2-F-02		Rev




Name: X:\G14002 Drawings\MEPA\FAB\M\F22P1-M-2-F-03.dwg User: nicky-3121 Date: 27/11/24 - 4:19pm





次 VER.	日期 DATE	修正者 REV BY	修 正 REVISION
			
台灣積體電路製造股份有限公司 Taiwan Semiconductor Manufacturing Company, Ltd.			
ACCEPTANCE REVIEWED		DATE	ACCEPTANCE REVIEWED
			DATE
CONTRACTOR			
 漢唐集成股份有限公司 United Integrated Services			
DRAWN	ROGER YEH	DATE	2024/02/21
RECHECKED	Sterven Yu	DATE	2024/02/21
DESIGNED	ROGER YEH	DATE	2024/02/21
APPROVED	JOSEPH LEE	DATE	2024/02/21
TITLE			
FLOW DIAGRAM- DUCTING SYSTEM (3) FAB			
PROJECT			
FAB22 Phase 1 PROJECT			
PACKAGE NAME			
MEP SYSTEM			
DRAWING NAME			
F22P1-M-2-F-07			
SCALE			UNIT
NOT TO SCALE			mm
FILE NAME			Rev.
F22P1-M-2-F-07			

Name: X:\G140W2_Drawings\MELP\ABM\1-M-2-F-07.dwg User: nicky-3121 Date: 2/1/11 4:20pm



KEY PLAN

Building Code

- A: Office
- F: FAB
- H: HPM
- C: CUP
- G: Gas Yard & BSGS
- S: Supporting
- N: ASC
- W: Warehouse

版本	日期	修正者	修正

tsmc

台灣積體電路製造股份有限公司
Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE

CONTRACTOR

uis 漢唐集成股份有限公司
United Integrated Services


DRAWN	ROGER YEH	DATE	2024/02/27	RECHECKED	Steven Yu	DATE	2024/02/27
DESIGNED	ROGER YEH	DATE	2024/02/27	APPROVED	JOSEPH LEE	DATE	2024/02/27

TITLE



FLOW DIAGRAM-
UPW/DI MAKE UP WATER SYSTEM
(1)
FAB

PROJECT	FAB22 Phase 1 PROJECT
PACKAGE NAME	MEP SYSTEM
DRAWING NAME	F22P1-M-2-F-08
SCALE	NOT TO SCALE
FILE NAME	F22P1-M-2-F-08

UNIT	mm
Rev	



ACCEPTANCE REVIEWED				DATE			
CONTRACTOR				DATE			
DRAWN				DATE			
DESIGNED				DATE			
TITLE				DATE			
PROJECT				DATE			
PACKAGE NAME				DATE			
DRAWING NAME				DATE			
SCALE				DATE			
FILE NAME				DATE			

[illegible]

版次 VER.	日期 DATE	修正者 REV.BY	修 正 REVISION
------------	------------	---------------	-----------------



台灣積體電路製造股份有限公司
Taiwan Semiconductor Manufacturing Company, Ltd

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE
---------------------	------	---------------------	------




UIS 漢唐集成股份有限公司



DRAWN ROGER YEH	DATE 2024/02/27	RECHECKED Steven Yu	DATE 2024/02/27
DESIGNED ROGER YEH	DATE 2024/02/27	APPROVED JOSEPH LEE	DATE 2024/02/27

FLOW DIAGRAM-
CO2 EXHAUST SYSTEM
(2)
FAB B & HPM

PROJECT	FAB22 Phase 1 PROJECT	
PACKAGE NAME	MEP SYSTEM	
DRAWING NAME	F22P1-M-2-F-10	
SCALE	UNIT	
NOT TO SCALE	mm	
FILE NAME	F22P1-M-2-F-10	Rev.



Name: X:\G140\02_Drawings\MEP\FAB\MF22P1-M-2-F-11.dwg User: nicky-3121 Date: 27/11/24 - 4:20pm




ACCEPTANCE REVIEWED				DATE			
CONTRACTOR				DATE			
DRAWN				DATE			
DESIGNED				DATE			
TITLE				DATE			
PROJECT				UNIT			
PACKAGE NAME				Rev			
DRAWING NAME							
SCALE							
FILE NAME							

HPM

Serial number: 202501201326-14437217

出圖日期: 2024/02/27



KEY PLANT

Building Code

- A: Office
- F: FAB
- C: CUP
- G: Gas Yard & BSGS
- S: Supporting
- N: ASC
- W: Warehouse

版本	日期	修正者	修正

tsmc

台灣積體電路製造股份有限公司
Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE

CONTRACTOR

uis 漢唐集成股份有限公司
United Integrated Services

DRAWN	ROGER YEH	DATE	2024/02/27	RECHECKED	Steven Yu	DATE	2024/02/27
DESIGNED	ROGER YEH	DATE	2024/02/27	APPROVED	JOSEPH LEE	DATE	2024/02/27

TITLE

**FLOW DIAGRAM-
PIPING SYSTEM
(2)
HPM**

PROJECT

FAB22 Phase 1 PROJECT

PACKAGE NAME

MEP SYSTEM

DRAWING NAME

F22P1-M-2-H-02



SCALE	UNIT
NOT TO SCALE	mm

FILE NAME


F22P1-M-2-H-02




Serial number: 202501201326-14437217

出圖日期: 2024/02/27





版本 VER.	日期 DATE	修正者 REV BY		修正 REVISION					
									
台灣積體電路製造股份有限公司 Taiwan Semiconductor Manufacturing Company, Ltd.									
ACCEPTANCE REVIEWED		DATE		ACCEPTANCE REVIEWED		DATE			
CONTRACTOR									
 漢唐集成股份有限公司 United Integrated Service									
DRAWN		ROGER YEH		DATE 2024/02/27		RECHECKED Steven Yu		DATE 2024/02/27	
DESIGNED		ROGER YEH		DATE 2024/02/27		APPROVED JOSEPH LEE		DATE 2024/02/27	
TITLE									
FLOW DIAGRAM- DUCTING SYSTEM (1) HPM									
PROJECT									
FAB22 Phase 1 PROJECT									
PACKAGE NAME									
MEP SYSTEM									
DRAWING NAME									
F22P1-M-2-H-03									
SCALE								UNIT	
NOT TO SCALE								mm	
FILE NAME					Rev.				
F22P1-M-2-H-03									





BSGS

[illegible]

台灣積體電路製造股份有限公司
Taiwan Semiconductor Manufacturing Company, Ltd.

ACCEPTANCE REVIEWED	DATE	ACCEPTANCE REVIEWED	DATE
---------------------	------	---------------------	------

CONTRACTOR
 漢唐集成股份有限公司
 United Integrated Services

DRAWN	ROGER YEY	DATE	2024/02/27	RECHECKED	STEVEN YU	DATE	2024/02/27
DESIGNED	ROGER YEY	DATE	2024/02/27	APPROVED	JOSEPH LEE	DATE	2024/02/27

TITLE

FLOW DIAGRAM -
PIPING & DUCTING SYSTEM
(1)
BSGS

PROJECT	FAB22 Phase 1 PROJECT
---------	-----------------------

PACKAGE NAME	MEP SYSTEM
--------------	------------

DRAWING NAME	F22P1-M-2-G-01
--------------	----------------

SCALE	UNIT
	mm

NOT TO SCALE	1000

FILE NAME	F22P1-M-2-G-01	Rev.
-----------	----------------	------

